PCT

INTERNATIONAL APPLICATION PUBLISHED UNDER THE PATENT COOPERATION TREATY (PCT)

(51) International Patent Classification 7 : C12Q 1/00, 1/48, G01N 33/543	**A1**	**(11) International Publication Number:** WO 00/42213 **(43) International Publication Date:** 20 July 2000 (20.07.00)

(21) International Application Number: PCT/US00/00803

(22) International Filing Date: 13 January 2000 (13.01.00)

(30) Priority Data:
60/115,643   13 January 1999 (13.01.99)   US

(71) Applicant: THE RESEARCH FOUNDATION OF STATE UNIVERSITY OF NEW YORK [US/US]; Suite 200 UB Commons, Amherst, NY 14228-2567 (US).

(72) Inventors: HANGAUER, David, G., Jr.; 8431 Hidden Oak Drive, East Amherst, NY 14051 (US). MARSILJE, Thomas, H.; 84 Tracey Street, Buffalo, NY 14201 (US). MILKIEWICZ, Karen, L.; 665 Kenmore Avenue, Buffalo, NY 14223 (US).

(74) Agents: GOLDMAN, Michael, L. et al.; Nixon, Hargrave, Devans & Doyle LLP, Clinton Square, P.O. Box 1051, Rochester, NY 14603 (US).

(81) Designated States: AE, AL, AM, AT, AU, AZ, BA, BB, BG, BR, BY, CA, CH, CN, CU, CZ, DE, DK, EE, ES, FI, GB, GD, GE, GH, GM, HR, HU, ID, IL, IN, IS, JP, KE, KG, KP, KR, KZ, LC, LK, LR, LS, LT, LU, LV, MD, MG, MK, MN, MW, MX, NO, NZ, PL, PT, RO, RU, SD, SE, SG, SI, SK, SL, TJ, TM, TR, TT, UA, UG, UZ, VN, YU, ZA, ZW, ARIPO patent (GH, GM, KE, LS, MW, SD, SL, SZ, TZ, UG, ZW), Eurasian patent (AM, AZ, BY, KG, KZ, MD, RU, TJ, TM), European patent (AT, BE, CH, CY, DE, DK, ES, FI, FR, GB, GR, IE, IT, LU, MC, NL, PT, SE), OAPI patent (BF, BJ, CF, CG, CI, CM, GA, GN, GW, ML, MR, NE, SN, TD, TG).

Published

With international search report.
Before the expiration of the time limit for amending the claims and to be republished in the event of the receipt of amendments.

(54) Title: A NOVEL METHOD FOR DESIGNING PROTEIN KINASE INHIBITORS

(57) Abstract

The present invention provides a method for identifying inhibitors of protein kinases. Methods are also provided for inhibiting protein kinase activity. Specific non-peptide protein tyrosine kinase inhibitor are provided. The protein kinases produced using the method of the present invention may be used to treat a number of conditions in patients, including cancer, psoriasis, arthrosclerosis, or immune system activity.

A NOVEL METHOD FOR DESIGNING
PROTEIN KINASE INHIBITORS

The present application claims the benefit of U.S. Provisional Patent

5   Application Serial No. 60/115,643, filed January 13, 1999.

BACKGROUND OF THE INVENTION

Protein kinases are a large class of enzymes which catalyze the transfer of the

10   γ-phosphate from ATP to the hydroxyl group on the side chain of Ser/Thr or Tyr in

proteins and peptides and are intimately involved in the control of various important

cell functions, perhaps most notably: signal transduction, differentiation and

proliferation. There are estimated to be about 2,000 distinct protein kinases in the

human body (Hunter, 1987, 1994, Hanks & Hunter, 1995), and although each of these

15   phosphorylate particular protein/peptide substrates, they all bind the same second

substrate ATP in a highly conserved pocket.

Inhibitors of various known protein kinases could have a variety of therapeutic

applications provided sufficient selectivity, and acceptable *in vivo* pharmacological

properties, can be incorporated into such inhibitors (Levitzki, 1996a). Perhaps the

20   most promising potential therapeutic use for protein kinase inhibitors is as anti-cancer

agents. This potential application for protein tyrosine kinase ("PTK") inhibitors has

been highlighted in many recent reviews (e.g. Lawrence & Hiu, 1998, Kolibaba &

Druker, 1997, Showalter & Kraker, 1997, Patrick & Heimbrook, 1996, Groundwater

et al., 1996, Levitzki, 1995). The foundation for this application is based partly upon

25   the fact that about 50% of the known oncogene products are PTKs and their kinase

activity has been shown to lead to cell transformation (Yamamoto, 1993).

The PTKs can be classified into two categories (Courtneidge, 1994), the

membrane receptor PTKs (e.g. growth factor receptor PTKs) and the non-receptor

PTKs (e.g. the src family of proto-oncogene products). There are at least 9 members

30   of the src family of non-receptor PTK's with pp60[c-src] (hereafter referred to simply as

"src") being the prototype PTK of the family wherein the ca. 300 amino acid catalytic

domains are highly conserved (Rudd et al.. 1993, Courtneidge, 1994). The

hyperactivation of src has been reported in and number of human cancers, including

those of the colon (Mao et al., 1997, Talamonti et al., 1993), breast (Luttrell et al., 1994), lung (Mazurenko et a, 1992), bladder (Fanning et al., 1992) and skin (Barnekow et al., 1987) as well as in gastric cancer (Takeshima et al., 1991), hairy cell leukemia (Lynch et al., 1993) and neuroblastoma (Bjelfman et al., 1990).

5   Overstimulated cell proliferation signals from transmembrane receptors (e.g. EGFR and p185HER2/Neu) to the cell interior also appears to pass through src (Mao et al., 1997, Parsons & Parsons, 1997, Bjorge et al., 1996, Taylor & Shalloway, 1996). Consequently, it has recently been proposed that src is a universal target for cancer therapy (Levitzki, 1996) because its' hyperactivation (without mutation) is involved in

10   tumor initiation, progression and metastasis for many important human tumor types.

In view of the large, and growing, potential for inhibitors of various protein kinases, a variety of approaches to obtaining useful inhibitors is needed. The status of the discovery of PTK inhibitors (Lawrence & Niu, 1988, Showalter & Kraker, 1997, Patrick & Heimbrook, 1996, Groundwater et al., 1996, Budde et al., 1995, Levitzki &

15   Gazit, 1995) has been extensively reviewed. Random screening efforts have been successful in identifying non-peptide protein kinase inhibitors but the vast majority of these bind in the highly conserved ATP binding site. A notable recent example of such non-peptide, ATP-competitive, inhibitors are the 4-anilinoquinazolines, and analogs, which were shown to be effective against the epidermal growth factor

20   receptor PTK (EGFRTK) (e.g. Rewcastle et al., 1996). Although this class of inhibitors was reported to be selective for the EGFR PTK vs. six other PTKs (including src, Fry et al., 1994) it is unknown what their effect is on most of the remaining 2,000 protein kinases that all bind ATP as well as a large number of other ATP, ADP, GTP, GDP, etc. utilizing proteins in the body. Therefore, potential side

25   effects from PTK inhibitor drugs that mimic ATP, which might only be discovered after expensive animal toxicity studies or human clinical trials, are still a serious concern. Also, although this class of compounds was a nice discovery and is undergoing further exploration, they do not provide a rational and general solution to obtaining non-peptide inhibitors for any desired PTK, e.g. in this case src. The risk of

30   insufficient specificity in vivo with ATP-competitive PTK inhibitors has also been noted by others, along with the inherent three order of magnitude reduction in potency these inhibitors display when competing with the mM levels of intracellular ATP

rather than the μM levels used in the isolated enzyme assays (e.g. see Lawrence & Niu, 1998, Hanke et al., 1996, Kelloff et al., 1996).

An older, and more extensively studied, class of non-peptide PTK inhibitors is erbstatin and the related tyrphostins (see reviews). This class of inhibitors are active against the receptor PTKs and their mode of inhibition is complex but does not appear to involve binding in the peptide substrate specificity site regions of the active site (Hsu et al., 1992, Posner et al., 1994). Furthermore, they are inactive against the isolated PTK when the *unnatural* assay metal Mn^{2+} is replaced with the *natural* Mg^{2+} (Hsu et al., 1992), are chemically unstable (Budde et al., 1995, Ramdas et al., 1995 & 1994), and are know to be cytotoxic to normal and neoplastic cells by crosslinking proteins (Stanwell et al., 1995 & 1996) as well as inhibit cell growth by disrupting mitochondria rather than PTK inhibition (Burger et al., 1995).

An important contribution to the protein kinase field has been the x-ray structural work with the serine kinase cAMP-dependent protein kinase ("PKA") bound to the 20-residue peptide derived from the heat stable inhibitor protein, PKI(5-24), and Mg_2ATP (Taylor et al., 1993). This structural work is particularly valuable because PKA is considered to be a prototype for the entire family of protein kinases since they have evolved from a single ancestral protein kinase. Sequence alignments of PKA with other serine and tyrosine kinases have identified a conserved catalytic core of about 260 residues and 11 highly conserved residues within this core (Taylor et al., 1993). Two highly conserved residues of particular note for the work proposed herein are the general base Asp-166 which is proposed to interact with the substrate OH and the positively charged residue, Lys-168 for serine kinases and an Arg for tyrosine kinases (Knighton et al., 1993), which is proposed to interact with the γ-phosphate of ATP to help catalyze transfer of this phosphate. Two additional important PKA crystal structures have been reported (Madhusudan et al., 1994), one for the ternary PKA:ADP:PKI(5-24) complex wherein the PKI Ala 21 has been replaced with Ser (thereby becomming a substrate), and one for the binary PKA:PKI(5-24) complex wherein the PKI Ala 21 has been replaced with phosphoserine (an end product inhibitor). The ternary complex shows the serine OH donating a H-bond to Asp-166 and accepting a H-bond from the side chain of Lys 168. The binary complex shows the phosphate group of phosphoserine forming a salt

- 4 -

bridge with the Lys-168 side chain and within H-bonding distance of the Asp-166 carboxyl group. These structures support the earlier proposed roles for Asp-166 and Lys-168 in the catalytic mechanism.

5   The x-ray structures of PKA show that the enzyme consists of two lobes wherein the smaller lobe binds ATP and the larger lobe the peptide substrate. Catalysis occurs at the cleft between the lobes. The crystallographic and solution structural studies with PKA have indicated that the enzyme undergoes major conformational changes from an "open" form to the "closed" catalytically active form as it binds the substrates (Cox et al., 1994). These conformational changes are

10   presumed to involve the closing of the cleft between the two lobes as the substrates bind bringing the γ-phosphate of ATP and the Ser OH in closer proximity for direct transfer of the phosphate.

However, the inhibitors of protein kinases still lack the specificity and potency desired for therapeutic use. Due to the key roles played by protein kinases in a

15   number of different diseases, including cancer, psoriasis, arthrosclerosis, and their role in regulating immune system activity, inhibitors of specific protein kinases are needed. The present invention provides a novel approach for designing protein kinase inhibitors, which are more potent as well as being more specific for the targeted pathways.

20

SUMMARY OF THE INVENTION

The present invention provides a method for identifying inhibitors of protein kinases. A first module having a one or more functional groups for binding to

25   catalytic residues of the protein kinase is combined with a second module which provides a non-peptide scaffold. Combinations of the first and second modules which inhibit protein kinase activity are selected.

The present invention also provides a method of inhibiting a protein kinase. The protein kinase is contacted by a compound comprising a first module having a

30   functionality for binding to catalytic residues of the protein kinase and a second module which provides a non-peptide scaffold. The combination of the first and second modules inhibits the protein kinase activity.

In a further embodiment, the invention provides a non-peptide protein tyrosine kinase inhibitor having the formula:

5

wherein wherein R1 is H or OH, R2 is H or OH, R3 is OH or H, and R4 is CH_3, $CH_2(CH_3)R$, or $CH_2(CH_3)S$, R5 is OCH_3, H, or OH, R6 is OCH_3, F, H, or OH, and R7 is OCH_3, H, OH, CO_2H, CO_2CH_3, CH_2CO_2H, or $CH_2CO_2CH_3$.

The present invention also provides a non-peptide protein tyrosine kinase inhibitor having the formula:

15

wherein R1 is OH or H, R2 is OH or H, R3 is OH or H, R4 is OH or H, R5 is OH, OMe, or H, R6 is OH, OMe, or H, R7 is OH, OMe, or H, and X is 0 or 1.

In yet another embodiment, the present invention provides a method of treating a condition, responsive to a protein kinase inhibitor, in a patient. A protein kinase inhibitor is administered to a patient. The protein kinase inhibitor has a first module having a functionality for binding to catalytic residues of the protein kinase and a second module which provides a non-peptide scaffold. The combination of the first and second modules inhibits protein kinase activity in the patient.

BRIEF DESCRIPTION OF THE DRAWINGS

Figure 1 depicts the modular strategy for developing non-peptide protein kinase inhibitors. Step 1 utilizes one or more first modules ("M_1's") to identify

- 6 -

promising non-peptide scaffolds. Step 2 enhances the potency by adding specificity elements. During this step the scaffolds are validated. Whether the inhibitor is non-ATP competitive can also be determined. In step 3, the potency and selectivity are further enhanced using combinatorial libraries to optimize M_1 and specificity

5   elements.

Figure 2 provides a depiction of the x-ray structure of (PKA):Mg_2ATP:pseudosubstrate inhibitor.

Figure 3 provides a general module M_1 design features for binding to the conserved protein kinase catalytic region.

10   Figure 4 shows that the boronic acid "inhibitors" <u>21</u> and <u>22</u> were shown to be substrates for PKA.

Figure 5 demonstrates the binding interactions of src substrate Ac-Ile-Tyr-Glu-Phe-NH_2 in model src active site.

Figure 6 shows the design of naphthalene-based src inhibitor scaffolds.

15   Figure 7 shows the design of isoquinoline and indole-based src inhibitor scaffolds.

Figure 8 provides an example of the chemistry used to prepare the naphthalene inhibitors, which is described in Marsilje 2000. A boronic acid functionality can be put put in place of a M_1 hydroxyl groups in the src inhibitors from Table 5 using the

20   Pd (0)-catalyzed cross-coupling methodology was used wherein either an aryl triflate (Ishiyama et al, 1997) or an aryl halide (Ishiyama, 1995) can be coupled with the commercially available pinacol ester of diboron.

Figure 9 shows a synthetic scheme that can be followed, in order to attach hydrophobic S_2 selectivity elements to the naphthalene scaffold.

25   Figure 10 shows successful model reactions with naphthalene chemistry, which can be converted to the solid phase in preparation for synthesizing combinatorial libraries of this scaffold in a 96-well plate format. The chemistry has been carried out on the less active naphthalene regioisomer represented by <u>44</u> because this compound is readily obtained from commercially available 3,5-dihydroxy-2-

30   naphthoic acid as describe in Marsilje 2000.

Figure 11 provides a possible strategy for modifying the naphthalene scaffold in combinatorial libraries.

Figure 12 shows the conversion of the triflate functionality formed in reaction 2 from intermediate 69 (Figure 11) to an amine (Wolfe et al, 1997) and then a series of amides or other amine derivatives.

Figure 13 Following the modeling procedure described above, a the series of hydroxy-containing analogs of the boronic acid M_1 group shown in Figure 13 were modeled in the src and IRTK (insulin receptor protein tyrosine kinase) active sites and found the illustrated interactions/binding modes as some of the interesting possibilities.

Figure 14 shows results from testing of the non-peptide src inhibitor 43-meta (Table V) in theLA25 and NRK cell lines.

Figure 15A shows a comparison of taxol and doxorubicin (they were more effective than etoposide & cisplatin in this tumor cell culture) with the three Src inhibitors mentioned above utilizing ovarian tumor cells from tumor N015. Figure 15B shows the results from tests of the src inhibitors for inhibition of normal human fibroblast cell growth. No inhibition of normal cell growth (both subconfluent and confluent; some enhanced growth was observed instead) was found, indicating that these inhibitors are not toxic to normal cells even at a 10-fold higher concentration. Figure 15 C provides the structures of the src inhibitors TOM 2-32, TOM 2-47, and KLM 2-31.

DETAILED DESCRIPTION OF THE INVENTION

The present invention provides a method for identifying inhibitors of protein kinases. The general modular strategy for the development of non-peptide PTK inhibitors is outlined in Figure 1. Basically, a first module having a one or more functional groups for binding to catalytic residues of the protein kinase is combined with a second module which provides a non-peptide scaffold. Combinations of the first and second modules which inhibit protein kinase activity are then selected. Step 1 begins with protein kinase inhibitor information which was already generated, i.e. pentapeptide scaffolds which bind in the substrate specificity sites of PKA or src have already been used to position various rationally designed functional groups (i.e. module "M_1" or "first module") to interact with the conserved catalytic residues, MgATP or MgADP. A selection of preferred functional groups have now been

- 8 -

identified in this fashion to serve as the initial M_1 module for Step 1. These M_1 functional groups have been utilized to identify promising non-peptide scaffolds for src inhibitors in Step 1. It was anticipated that these bare non-peptide scaffolds, with only an M_1 appendage, would have low binding affinity and be relatively non-

5   selective among the PTKs. A lack of selectivity at the level of Step 1 is viewed as an advantage for the development of a general strategy which can be reapplied to additional PTKs. Therefore the suite of non-peptide scaffolds identified in Step 1 can be recycled for use against additional PTKs by rescreening them and carrying the better ones through Steps 2 and 3, all using the new PTK target. The potency of these

10   bare scaffolds from Step 1 may be increased enough by the attachment of one or two initial specificity elements (S_n) to allow for the validation of the scaffold as non-ATP competitive and amenable to further potency enhancements using combinatorial chemistry in a rationally guided fashion. Promising src non-peptide M_2 (second module) scaffolds identified in Step 1 have undergone Step 2 and displayed a one to

15   two order-of-magnitude increase in potency against src as well as non-competitive binding relative to ATP.

       Validation of the scaffolds at the level of Step 2 before undertaking the resource intensive combinatorial library synthesis and testing of Step 3 is important for three reasons: 1) To develop the chemistry for appending the specificity element

20   (S_n) side chains. 2) To determine that these inhibitors are not ATP-competitive. 3) To determine that the potency is responding to the side chain S_n properties and attachment points as would be expected based upon the working model for the src:inhibitor complex (this provides some confidence that rationally guided choices can be made for the ranges of individual selectivity elements S_n to include in the

25   focused libraries of Step 3).

       It is in Step 3 that high potency and specificity for a particular PTK is anticipated because numerous combinations of M_1 functional groups (and close analogs M_1') with selectivity elements (S_n) will be evaluated experimentally via combinatorial chemistry and high-throughput screening. Potency and selectivity may

30   be further increased if necessary by appending additional specificity elements (see optional S_n's in Figure 1). One of the selected src inhibitor scaffolds from Step 2 has already been attached to a solid phase resin and is currently being developed into a combinatorial library following Step 3.

-9-

In each of the Steps 1-3, molecular modeling studies with the IRTK:peptide:AMP-PNP crystal structure, the model of the src:peptide complex and the models for the src complex with the individual families of inhibitors based upon a particular scaffold will be used as qualitative guides. These modeling studies have

5   been remarkably helpful thus far in guiding the inhibitor design efforts as detailed later. Combining structure-based design and combinatorial chemistry technologies in this fashion provides a synergy wherein the major individual deficiencies of these technologies used in isolation are addressed by the strengths of the other. The major deficiency of structure-based design is the difficulty in quantitatively predicting

10   ligand binding affinities, which is particularly challenging due to the complex effects of solvation and entropy (Ajay & Murcko, 1995). The major strength of structure-based design is its' capability to predict what types of molecules are likely to be good ligands. Structure-based design can determine the rough boundaries (proteins have some flexibility which need to be taken into account) for molecular size and shape as

15   well as indicate where hydrophobic, H-bonding and ionic interactions are likely to occur. On the other hand, the major deficiency of combinatorial chemistry is that "molecular space" for drug-sized molecules (i.e. MW ca. 500 or less) is so large that one could not hope to sample all of this molecular space with a high density of coverage in a reasonable sized combinatorial library. A recent estimate (Bohacek et

20   al., 1996) of the number of possible compounds containing up to 30 atoms chosen only from carbon, nitrogen, oxygen and sulfur (in addition to H's) is 10^{60} compounds. This is in the molecular weight range of typical drug molecules and still does not include additional diversity provided by other atoms, e.g. halogens. Consequently, additional constraints need to be used to identify regions of molecular space wherein

25   particular drug candidates are likely to be located. Structure-based design can drastically reduce the volume of molecular space to be explored by identifying the types of molecules which have a higher probability of being good ligands. The inability to quantitatively predict which of these "focused" combinatorial library members will in fact be the tightest binding ligands (i.e. the quantitation problem) is

30   then resolved by employing an efficient combinatorial synthesis and high-throughput testing of the library.

In the earlier peptide based serine and tyrosine kinase inhibitor design efforts PKA was used as a convenient qualitative model for designing the protein kinase

inhibitor module M_1 for interaction with the conserved catalytic residues. There is much more structural and kinetic information available for PKA than any other protein kinase.

5   The crystal structure of PKA complexed with Mg2ATP and a pseudosubstrate (i.e. OH replaced with H) peptide inhibitor (PKI 5-24 amide) has been solved (Zheng et al., 1993) and the active site interactions near the P 0 Ala of this inhibitor are shown in Figure 2.

This crystal structure shows Mg2ATP bound to the small lobe of PKA and a 20-residue pseudosubstrate peptide inhibitor bound to the large lobe with the overall
10   conformation of the enzyme in the closed (i.e. the two lobes are touching) and activated state. The distances between the P 0 Ala side chain carbon and the nearby heavy atoms in the complex are shown in A^0 in Figure 1. These distances show that the Ala side chain is within van der Waals contact distance of the surrounding atoms and indicates that there is little space for appending bulky M_1 functional groups to the
15   Ala side chain. However, PKA is a flexible enzyme with open, closed and intermediate conformations (Cox et al., 1994) and these more open conformations would result in a retraction back of the ATP γ-phosphate from the inhibitor Ala thereby creating a binding cavity for appended M_1 functional groups. Furthermore, PKA binds MgADP with the same affinity as MgATP (Whitehouse et al., 1983) and
20   the ratio of ATP/ADP in cells is typically 10/1 (Alberts, et al. 1994). Therefore, at equilibrium, ca. 10% of the cellular protein kinase is in the MgADP bound state and this form of the enzyme can also be targeted with an inhibitor to drain all of the enzyme from the catalytic cycle into a PKA:MgADP:inhibitor inactive complex.

Since the PKA catalytic residues Asp-166 and Lys-168 are completely
25   conserved in all serine kinases, and the tyrosine kinases only differ by the substitution of Arg for Lys-168 (Taylor et al., 1993), this region of the active site was chosen, along with the adjoining MgATP or MgADP, to target a selection of inhibitor functional groups which could serve as M_1 and be broadly useful for developing inhibitors for the entire protein kinase family. By targeting M_1 to the region of the
30   active site adjacent to the nucleotide, an orientation point is provided for the non-peptide inhibitors which can extend into the peptide binding specificity sites without always competing with ATP/ADP binding.

A selection of functional groups which could be utilized as M_1 was identified first because, although this region of the active site is very highly conserved, it was expected that each particular protein kinase will still display some differing preferences across this selection due to small variations in the active site conformations and adjoining residues. Furthermore, the rank order preference among this selection of M_1's may change somewhat as the M_1 module is appended to different non-peptide scaffolds. This expectation is based upon the potential for each non-peptide scaffold to bind in somewhat different orientations with each individual protein kinase and with each particular set of selectivity element (S_n) side chains. Pentapeptide scaffolds were chosen for the initial screening of functional groups for M_1 because the binding orientation of these larger peptide scaffolds is likely to be very consistent and predictable (i.e. closely resembling that observed by x-ray) throughout the series and could be more confidently assumed to position each tested M_1 functionality adjacent to the conserved catalytic residues as intended. Consequently, the goal of this earlier peptide-based work was to identify a collection of M_1 functional groups which can be used, not only for the initial screening of non-peptide scaffolds (Step 1), but also as an initial set of M_1 side chains which can be further expanded via close analogs and thereby optimized simultaneously with the other side chains in the final non-peptide combinatorial libraries (Step 3).

In order to model the candidate M_1 functional groups in this conserved catalytic region of the PKA active site, they were built onto the P 0 Ala position in the PKA ternary structure using the SYBYL molecular modeling package (Tripos) on a Silicone Graphics workstation as indicated in Figure 3.

A crystal structure of PKA with MgATP and an inhibitor bound in a more "open" conformation was not available, so initial modeling studies were carried out on the MgADP bound form of PKA derived from the ternary complex illustrated in Figure 2 by simply deleting the ATP γ-phosphate. Initial modeling studies were used to provide qualitative guidance for identifying interesting potential M_1 functional groups for the protein kinase family before synthesis and testing. The most advanced computational algorthms for quantitatively predicting the free energy of binding, such as Free Energy Perturbation methods, are computationally intensive methods which are not practical at this point in time for routine use by the non-specialist. Even the most advanced methods can be inaccurate due to difficulties in sampling,

- 12 -

inadequacies in the molecular mechanics force fields/parameters, and an incomplete understanding of electrostatics in water (Ajay & Murcko, 1995). Less rigorous (and easier to use) computational methods tend to be unreliable in making quantitative predictions of binding affinities, especially when dealing with multiple polar and ionic

5   interactions such as those involved in M_1 binding.

In order to allow molecular mechanics calculations to be done with the Silicone Graphics workstation in a reasonable amount of time, two layers of residues were carved out from the PKA ternary structure which are surrounding the PKA active site, along with the peptide inhibitor and Mg_2ADP. The M_1 functional groups

10   were then appended to the P 0 Ala side chain and the entire PKA active site:Mg_2ADP:modified peptide inhibitor complex was then subjected to 300 iterations of molecular mechanics minimization using the Tripos force field with a distance dependent dielectric constant after assigning appropriate formal charges and calculating Gasteiger Marsili point charges using SYBYL. Setting the maximum

15   number of iterations at 300 was sufficient to remove any serious strain in the complexs and yet not allow the overall structure to "drift" significantly from the starting x-ray structure if convergence is not reached. These minimized complexes were then visually evalulated to determine if the appended individual M_1 functional groups were able to engage in favorable interactions with the conserved catalytic

20   residues and/or Mg_2ADP. This visual evalulation involved, among other standard interaction evaluations, measuring atom-atom distances to determine if hydrogen bonds and ionic interactions were being favorably formed.

Favorable intermolecular interactions between an individual M_1 functionality and the conserved catalytic residues or Mg_2ADP does not necessarily mean enhance

25   binding affinity will be observed for the new inhibitor. Unfavorable desolvation of both the polar M_1 functionality and the polar PKA active site residues (as well as complex entropy effects) are not included in this analysis and may reduce the net binding affinity to the point that the modified inhibitor may even be less potent that the corresponding P 0 Ala inhibitor, even though the appended M_1 functionality *is*

30   interacting with the conserved catalytic residues and/or MgADP (or MgATP) as intended. Even in cases where this desolvation penalty results in no net increase in binding affinity, these M_1 functional groups are still useful as an orienting groups for correctly positioning the non-peptide inhibitor analogs in the protein kinase active

- 13 -

site. Positioning these polar functional groups elsewhere within the active site (assuming they are tethered so as not to be able to extend into bulk solvent while the scaffold is favorably bound in the active site) is likely to result in a reduced binding affinity because they were specifically designed and selected based upon their

5   demonstrated ability (while appropriately tethered to pentapeptide scaffolds) to be accepted adjacent to the conserved catalytic residues and MgADP/MgATP. If a particular M_1 functionality does not correctly position a non-peptide scaffold in Step 1 then attempts to improve the potency by rationally appending initial specificity elements in Step 2 would likely fail.

10   None of the literature protein kinase assay procedures contain added ADP. A typical PKA literature assay procedure (Glass et al., 1989) was modified by adding 10% as much ADP as the ATP concentration used to reflect the natural 1/10 ratio in the cell. This protein kinase assay is hereinafter referred to as the "Literature Mimetic" assay. It has been used for PKA as well as the src. An examination of the

15   literature, and commercially available protein kinase assays, showed that there is poor consistency from lab to lab and company to company and that all of these assays use physical chemical conditions which differ considerably from those known to exist inside cells. Since inhibition of intracellular protein kinases is the ultimate goal for drug discovery, new protein kinase assays have been developed which come much

20   closer to mimicking the overall cytosolic physical chemical conditions known to exist inside cells. The development of these "Cellular Mimetic" protein kinase assays, is described herein, along with a novel method for determining which form of a protein kinase a given inhibitor binds best to (the STAIRe method). Data was collected correlating the activity of the new non-peptide src inhibitors in the Cellular Mimetic

25   assay with that obtained in the LA25 src transformed cell line (see below).

When these two assay conditions were applied to some of the pentapeptide-based PKA inhibitors, which were designed as illustrated in Figure 3, the results shown in Table 1 were obtained. The same assay conditions were also applied to the analogously designed pentapeptide-based src inhibitors and obtained the results

30   shown in Table 2.

The standard pentapeptide sequence chosen for the majority of PKA inhibitors in Table 1 was derived from the pseudosubstrate sequence of the peptide inhibitor which was bound to PKA, when the crystal structure illustrated in Figure 1 was

- 14 -

solved. The standard pentapeptide sequence used for src in Table 2, Ac-Ile-AA-Gly-Glu-Phe-NH$_2$, was described in Nair, Kim et al., 1995. Some of the chemistry used to prepare the PKA inhibitors is described in Nair, Lee & Hangauer 1995. The synthetic methodology used to develope a number of the src inhibitors is described in

5   Lai et al., 1998.

The collective results in Tables 1 and 2 show that both the serine kinase PKA and the PTK src can accommodate a variety of large polar M$_1$ functional groups at the P 0 phosphorylation position. Furthermore, using the STAIRe methodology (see Choi et al. 1996), the sulfamic acid inhibitor 8, and related inhibitors, were shown to

10   actually bind best when MgATP (not MgADP or no nucleotide) is also bound. This was a somewhat surprising result since these inhibitors are analogs of the "end product inhibitors" 1 & 12 which must bind simultaneously with MgADP just following phosphate transfer in the generally accepted reaction mechanism for protein kinases.

15   These results also demonstrate that both PKA and src can show a large difference in binding affinity for structurally very similar inhibitors. For example, the sulfamic acid PKA inhibitor 8 (Table I) has a K$_i$ of 0.16 µM under Literature Mimetic assay conditions (L) whereas the isosteric sulfonamide 7 is 1,875 X less potent (K$_i$ = 300 µM). The sulfamic acid inhibitor 8 is also isosteric with the end product

20   phosphate inhibitor 1 yet it binds much more tightly under both Literature Mimetic assay conditions (31 X) and Cellular Mimetic (C) assay conditions (108 X). The beneficial effect of an oxygen atom positioned analogously to that in the substrate Ser is illustrated by comparison of phosphonate 2 to phosphate 1 and also ether 6 to phosphate 1. This oxygen atom can also be positioned as a serine-like OH side chain

25   and enhance binding (compare 2 to 3A and 4A) wherein the closer serine mimic 4A is the more active. The difference in activity of the diasteromeric inhibitors 3A or B and 4A or B suggests a specific interaction with the active site catalytic residue Asp-166 may in fact be occurring as intended in the M$_1$ design (Figure 3).

- 15 -

TABLE I
INITIAL M_1 SCREENING RESULTS WHILE APPENDED TO THE PKA PENTAPEPTDE SCAFFOLD

$$\text{Ac-Arg-Arg-Gly-NH} \overset{M_1}{\underset{O}{\diagdown}} \text{Ile-NH}_2$$

---- = Attachment Point

K_i (µM), (Conditions*)
* L=Literature Mimetic
C=Cellular Mimetic

K_i (µM), (Conditions*)
* L=Literature Mimetic
C=Cellular Mimetic

1 $M_1 =$ (End Product Inhibitor)   5 (L) / 542 (C)   108 X

7 $M_1 =$ 300 (L) / 2400 (C)   8 X

2 $M_1 =$ 76 (L) / NT (C)

8 $M_1 =$ 0.16 (L) / 5 (C)   31 X

3 $M_1 =$ 18 (L)-Diastereomer A / 72 (L)-Diastereomer B / NT (C)

9 $M_1 =$ 250 (L) / 2100 (C)   8 X

4 $M_1 =$ 4 (L)-Diastereomer A / 20 (L)-Diastereomer B   43 X / 171 (C)-Diastereomer A / 1510 (C)-Diastereomer B

10 $M_1 =$ 38 (L) / 115 (C)   3 X

11 $M_1 =$ 45 (L) / NT (C)

$M_1 =$

5 X= H   28 (L) / 780 (C)   29 X

6 X= CO_2H 6 (L) / 450 (C)   75 X

The src inhibition results (Table II) show that the end product inhibitor **12** drops in activity upon going from Literature Mimetic assay conditions to the higher ionic strength Cellular Mimetic assay conditions analogous to the PKA end product inhibitor **1**. However, whereas all of the PKA inhibitors with polar M_1 functional groups were less active under Cellular Mimetic assay conditions three of the src inhibitors **14**, **15**, & **17** held their activity under these higher ionic strength assay conditions. Also, the hydroxyphosphonate src inhibitor **13** (a mixture of the R and S diastereomers) is analogous to the PKA inhibitor **3A** and both are roughly in the same

activity range as their corresponding end product inhibitors, 12 & 1 respectively, under Literature Mimetic assay conditions. Shortening the side chain length in the phosphonate src inhibitor 13 by one carbon atom (and necessarily removing the attached OH at the same time) to give 14 improved the activity (analogous to the PKA

5   inhibitor comparison 3 to 4) and, more importantly, resulted in equivalent activity under Cellular Mimetic assay conditions. The src results with 16-19 (particularly 17, see later for an analogous α-tricarbonyl acid M_1 analog appended to non-peptide src inhibitors) also suggests that similar amides may be useful M_1 functional groups to explore with non-peptide src inhibitors.

10   Non-peptide src inhibitors are preferred to peptide scaffold based compounds, partly because some of these inhibitors have a dual effect on src. For example, phosphonate inhibitor 14 not only inhibits src by competitively binding in the active site but it also activates src by binding to the SH2 site thereby releasing the intramolecular autoinhibition mechanism (Xu et al., 1997). This opposing effect

15   gives an unusual IC_{50} curve for 14 wherein at low inhibitor concentrations src is stimulated (to a maximum of 70%) in a smooth dose-response fashion (due to initial tighter SH2 binding) followed by a typical IC_{50} inhibition curve at higher inhibitor concentrations (due to lower affinity blockade of the active site). This opposing activation effect of the pentapeptide inhibitors makes them appear to be less potent

20   active site inhibitors than they in fact are, and makes it difficult to accurately rank M_1 groups while appended to this pentapeptide scaffold. However, the better M_1 groups identified with the src pentapeptide scaffold must still be accommodated in the catalytic region of the active site and hence are useful orienting groups for the ongoing non-pepitde src inhibitor studies as intended. Since PKA does not have an

25   SH2 domain this complication is not a factor in interpreting the PKA pentapeptide inhibitor M_1 testing data.

- 17 -

TABLE II
INITIAL M₁ SCREENING RESULTS WHILE APPENDED TO THE SRC PENTAPEPTIDE SCAFFOLD

M₁ structure appended to Ac-Ile-NH...Gly-Glu-Phe-NH₂ scaffold

Inhibitor (1 mM)	% Inhibition of 2 mM RR-src phosphorylation by src Assay Conditions		Inhibitor (1 mM)	Literature Mimetic	Cellular Mimetic
	Literature Mimetic	Cellular Mimetic			
12 M₁ =	36	0	16 M₁ =	60	8
13 M₁ =	51	0	17 M₁ =	20	28
14 M₁ =	83	88	18 M₁ =	64	5
15 M₁ =	68	59	19 M₁ =	24	0

The results in Tables 1 and 2 also show how much effect the assay conditions can have on both inhibitor potencies and the rank order of activity. For example, as shown in Table 1, switching from the Literature Mimetic (L) assay conditions to the Cellular Mimetic (C) assay conditions can change the potency from as little as 3-fold (inhibitor **10**) to as much as 108-fold (inhibitor **1**). Also, whereas inhibitor **10** is less potent than **1** under Literature Mimetic conditions it is more potent under Cellular Mimetic conditions. The src inhibitor data presented in Table 2 show that many of the inhibitors lose their potency upon going from Literature Mimetic assay conditions to Cellular Mimetic assay conditions. The rank order of potency against src is also sensitive to the assay conditions. Whereas inhibitor **18** is more potent than inhibitor **17** under Literature Mimetic conditions, the opposite is true under Cellular Mimetic conditions. Since activity within cells is the goal, the Cellular Mimetic src assay was selected as the standard assay for testing potential non-peptide src inhibitors. Activity within the Cellular Mimetic assay is a necessary, but not sufficient, condition for activity within cells. As will be described later, the Cellular Mimetic src assay will be followed up with cell culture assays wherein cell penetration, metabolism and binding to other cellular components are also factors in the measured potency.

The next class of M₁ functionality which was explored was the boronic acid group. This functional group is an intriguing candidate for M₁ for a number of reasons: 1) It can exist in a non-ionic state so that it should not prevent passive absorption of non-peptide inhibitors across cell membranes. 2) The planar, trigonal,

- 18 -

boron acids might form reversible tetrahedral covalent borate complexes (a well
known property of boronic acids, see Loomis & Durst,, 1992) through their vacant 2p
orbitals with anions present in the protein kinase active site such as the catalytic Asp
carboxyl group or the ATP/ADP terminal phosphate oxygens. This ability to form
5   borate complexes with active site nucleophiles has been extensively utilized to
develop slow binding inhibitors of serine proteases (e.g. see Kettner & Shenvi, 1984),
wherein the nucleophilic serine OH forms a covalent bond with the vacant 2p orbital
in the boronic acid resulting in a tetrahedral borate complex (e.g. see Skordalakes et
al., 1997). Also, an intramolecular complex of a boronic acid with a urea NH_2 was
10   used to prepare transition state analogs inhibitors of dihydroorotase (Kinder et al.,
1990). 3) Boronic acids act as Lewis acids and are converted to tetrahedral hydrates
in water by forming borate complexes with water or hydroxide ions. Therefore, it is
also possible that these boronic acid hydrates may function as phosphate mimics and
M_1 modules as proposed in Figure 2. This hydration property was utilized by Baggio
15   et al. (1997) wherein a hydrated boronic acid functioned as a transition state analog
inhibitor functionality for arginase. These researchers evaluated the inhibited
complex by x-ray and showed that the hydrated boronic acid functionality formed two
hydrogen bonds with the active site catalytic Glu-277 carboxyl side chain and one of
the other hydrated boronic acid OH's interacted with two catalytic Mn^{2+}'s in the
20   active site. These binding interactions are closely analogous to those proposed in
protein kinase active sites, i.e. H-bonds to the catalytic Asp side chain carboxyl group
and interactions with the active site Mg^{2+}'s (see Figure 2), and 4) The use of boronic
acids for protein kinase inhibitors has not been explored previously.

In the area of pentapeptide-based PKA inhibitors, the boronic acid
25   functionality has been prepared and tested as a potential M_1 module utilizing the four
inhibitors 21-24 shown in Table 3 (see Hsiao & Hangauer, 1998, for some of the
chemistry used to prepare these compounds).

- 19 -

TABLE III

PKA INHIBITION RESULTS WITH BORONIC ACID-CONTAINING PEPTIDE INHIBITORS

Ac-RRGXI-NH$_2$, X =	IC$_{50}$ µM (cond. L, 0 h preincubation)	IC$_{50}$ µM (cond. L, 4 h preincubation)	IC$_{50}$ µM (cond. C, 0 h preincubation)	IC$_{50}$ µM (cond. C, 4 h preincubation)
20 Ala	278 (K$_i$ =9 µM)	417	41 (K$_i$ = 25 µM)	50
21 (boronic acid structure, OH, B–OH, HN–CO)	249	* 500 µM 34% inh	764	* 2000 µM 19% sti
22 (boronic acid structure, OH, B–OH, HN–CO)	81	* 65	* 1753	* 2000 µM 71% sti
23 (boronic acid structure, HO–B–OH, HN–CO)	398	133	2000 µM 16% inh	* 2000 µM 5% inh
24 (boronic acid structure, OH, B–OH, HN–CO)	1000 µM 33% inh	1000 µM 44% inh	2000 µM 6% sti	1734 µM

* Very distorted IC$_{50}$ curve: Suggests Inhibitor is also a substrate.
L = Literature Mimetic Assay Conditions.   Inh = Inhibition.
C = Cellular Mimetic Assay Conditions.   Sti = Stimulation.

While testing these boronic acid-containing PKA inhibitors, the corresponding pentapeptide pseudosubstrate inhibitor **20** was included as an internal control while investigating time-dependent inhibition as shown in Table 3. Under Literature Mimetic assay conditions, and no preincubation, the initial results suggested that the shortest chain L-amino acid **21** was binding with the same affinity as the pseudosubstrate inhibitor **20** (i.e. K$_i$ ca. 9 µM). As this side chain was increased in length (to **23** and then **24**) binding affinity appeared to decrease. When the stereochemistry of the unnatural amino acid was inverted from L in **21** to D in **22**, binding affinity appeared to increase 3-fold. This improvement in binding may occur as a result that the boronic acid OH in **21** is positioned at the same chain length as L-homoserine whereas the natural substrate, L-serine, has a one carbon shorter side chain. Modeling results with the PKA ternary structure indicated that the boronic acid OH can be retracted back somewhat by inverting the α-carbon stereochemistry from L in **21** to D in **22** and then repositioning the side chain to more closely mimic the

- 20 -

positioning of the natural substrate L-serine OH adjacent to the catalytic residues (Asp-166 and Arg-168). The modeling results were subsequently supported by the finding that, upon incubation of PKA with these inhibitors for up to 4 hours without adding the competing peptide substrate (Kemptamide: LRRASLG-NH$_2$), both 21 and

5   22 function as substrates with the D-diastereomer 22 being phosphorylated faster.

The fact that these boronic acid inhibitors are also substrates, became much more obvious by the greatly distorted IC$_{50}$ curves obtained under the Cellular Mimetic conditions, both with and without preincubation (both PKA and src are more active enzymes under the Cellular Mimetic conditions than under Literature Mimetic

10   conditions). In the assay used to obtain these results, the P^{32} phosphorylated Kemptamide product (25 generated from γ-P^{32} ATP) was isolated at the end of the substrate incubation period by binding to phosphocellulose filter paper via the three cationic groups (two Arg's and the N-terminus) and the level of phosphorylated product isolated on the paper is then measured by liquid scintillation counting

15   (cpm's). The boronic acid inhibitors 21-24 have two Arg's in their sequence also and therefore will bind to the phosphocellulose paper in addition to Kemptamide (although not as consistently or completely due to one less positive charge). Consequently, when analyzed as inhibitors, the amount of phosphorylated Kemptamide produced was not only counted, but also the amount of phosphorylated

20   inhibitor simultaneously produced (e.g. see 26 below). The net result is that distorted IC$_{50}$ curves are obtained which show net "stimulation" at higher inhibitor concentrations in some cases. The D diastereomer 22 gives the greatest apparent "stimulation" (71%) when preincubated with PKA for 4 hours under Cellular Mimetic conditions followed by the L diastereomer 21 (19%) and then the one carbon homolog

25   23 (5%) indicating all three are substrates for PKA (Table III). The underlying substrate behavior of these "inhibitors" makes an accurate measurement of their inhibition potency impossible with the current assay. However, it does appear from the data that homologating the boronic acid functionality out with only CH$_2$ groups (homologations with boronic acid non-peptide src inhibitors may also be carried out)

30   decreases the binding affinity and ability to function as a substrate.

Phosphorylated Kemptamide

Compare with

Phosphorylated **22**

The boronic acid "inhibitors" **21** and **22** were shown to be substrates for PKA
by running the same assay, but without adding Kemptamide, and stopping the reaction
at various time points as shown in Figure 4. The graphs show their respective rates
and levels of phosphorylation with the typical loss of initial velocity kinetics with
time (due to substrate depletion and end product inhibition), analogous to a standard
L-Ser substrate such as Kemptamide. The comparison of **21** to **22** shown was done in
the same assay run, at identical boronic acid substrate concentrations, and with
identical Cellular Mimetic assay solutions so that the cpm's could be directly
compared. The graphs show that initial velocity conditions were lost within one hour
for D isomer **22** whereas the linearity appears to have been lost somewhat slower with
the L isomer **21** suggesting a slower consumption of starting material. That the
boronic acid moiety would be phosphorylated by PKA was surprising, but it is even
more surprising that the phosphonic-boronic acid mixed anhydride produced (e.g. **26**)
was stable enough to survive the pH 7.2/37°C assay incubation and then be isolated
by binding to phosphocellulose paper after acid quenching of the reaction with 10%
TCA and washing the phosphocellulose paper with 25 mM phosphoric acid (3X). An
STN substructure search was run on mixed anhydrides of phosphoric and boronic
acids and found only three references to experiments and theoretical calculations for
the analogous putative (but not proven) anhydride formed from boric acid and
phosphoric acid as a solid surface impregnated catalyst for the partial oxidation of
ethane to acetaldehyde at 823 °K (Zhanpeisov & Otsuka, 1992, Otsuka et al., 1992,
Murakami et al., 1990). However, this highly unusual anhydride has never before
been synthesized free of a solid surface, isolated or characterized. Thus, this is a
novel enzymatic reaction and chemical entity with interesting possibilities for protein
kinase inhibitor designs.

- 22 -

The src and PKA pentapeptide scaffold tethered M_1 evalulations described above have resulted in identifying a variety of orienting M_1 groups which could be used for screening potential non-peptide scaffolds as indicated in Step 1 (Figure 1). The boronic acid (from __22__), the phosphonate (from __14__), and the sulfamic acid (from

5   __8__) were initially chosen from the menu of potential M_1's for the src non-peptide scaffold screening. Among these choices, the boronic acid M_1 group has proven effective for Step 1 screening of non-peptide scaffolds.

The most useful crystal structures available for the design of non-peptide src inhibitors, which do not compete with ATP, are the native src structure and the

10   IRTK:peptide:AMP-PNP ternary structure. For all of the modeling studies discussed below, the SYBYL molecular modeling software package is used on a Silicone Graphics Workstation.

Since the src and IRTK structures are only used as qualitative guides in designing the non-peptide scaffolds and combinatorial libraries, the active sites along

15   with two layers of surrounding residues were carved out from the native src and IRTK ternary structures, analogous to the previous PKA modeling studies. The IRTK:peptide:AMP-PNP ternary structure active site region was used as the template structure to guide the building of the src residue sequence 424-418 back onto the src structure using the comparative homology modeling technique (see Hutchins & Greer,

20   1991). These residues were disordered in the native src crystal structure and therefore not visible by x-ray. They were reintroduced because they help form the P+1 to P+3 binding sites for peptide substrates which are important for some of the modeling studies. The analogous residues in the IRTK ternary structure are seen by x-ray and directly interact with the bound peptide substrate. In fact, it is probably the presence

25   of the bound peptide substrate which induces order in the positioning of this sequence so that it is visible by x-ray. The src pentapeptide substrate Ac-Ile-Tyr-Gly-Glu-Phe-NH_2 (Nair et al., 1995) was then docked into the src active site again using the IRTK ternary structure as a template. Small adjustments were then manually made to partially clean up this complex, all of the hydrogen atoms were added, appropriate

30   formal and partial charges (calculated via the Gasteiger Marsili method) were added, and then the entire complex was subjected to 300 iterations of molecular mechanics minimization using the Tripos force field, analgous to the previous PKA modeling procedure. A schematic representation of this modeled complex is given in Figure 5.

- 23 -

Any inaccuracies in this src:peptide and the src:inhibitor models are accommodated by experimentally evaluating a range of side chains, the number and diversity of which is scaled roughly to the level of uncertainty for the structure of their particular binding region in the src model active site (see later), in a combinatorial fashion.

5   As shown in Figure 5 the residues 424-418 built back into the src interact with the P+1 to P+3 substrate residues, Gly-Glu-Phe-NH$_2$ respectively, through beta sheet type hydrogen bonding interactions with the substrate main chain (analogous to the IRTK peptide substrate). Lys 423 engages in two important interactions: 1) the β and γ CH$_2$'s fold over the top of the P O Tyr phenyl ring engaging in a hydrophobic

10   binding interaction and then 2) the remaining CH$_2$-CH$_2$-NH$_3^+$ of this side chain extends away to form a salt bridge with the P+2 Glu side chain as indicated. The rest of the P 0 Tyr hydrophobic binding pocket is formed by Pro 425 under the phenyl ring and part of the Cys 277 side chain above the phenyl ring. Using a large combinatorial peptide src substrate library, Songyang et al. (1995) found that the most commonly

15   chosen side chain for the P+1 position was Gly followed by Glu. The present model indicates that a P+1 Glu side chain may form a salt bridge with nearby Arg 469 as indicated in Figure 5. Previously, researchers found that only Glu was chosen for the P+2 position and the present model indicates that this side chain forms a salt bridge with the Lys 423 side chain. At the P+3 position Phe was very strongly preferred and

20   the model indicates that this side chain forms a stacking interaction with the Phe 424 side chain. At the P-1 position Songyang et al. found that Ile was the most preferred residue followed by Val and then Leu. The model shows a hydrophobic pocket for binding the P-1 side chain formed mainly by Trp 428, Ala 390 and Leu 347. One might expect that the P 0 Tyr side main chain will strongly interact (though hydrogen

25   bonding) with the active site in a catalytically competent complex because enzymes often form more critical interactions in this region close to where the reaction will be occurring. The IRTK ternary complex does not show a good hydrogen bond to either the P 0 Tyr NH or carbonyl. The nearest candidate residue for this interaction in the IRTK structure is Asn 1215 wherein the side chain NH$_2$ is 3.71 A$^\circ$ from the Tyr

30   carbonyl oxygen. When the IRTK ternary structure is overlayed onto the src native structure, using the four residues mentioned in the Background and Significance section, Asn 468 from the src structure was found to be positioned very close to the analogous IRTK Asn 1215. This suggests that this conserved residue is performing

- 24 -

an important role and might move a little closer (i.e. about 1 A°) to the substrate P 0

NH and carbonyl in a catalytically active complex and form the hydrogen bonding

interactions indicated in Figure 5. Finally, the catalytic Arg 388 and Asp 386 are

correctly positioned in the src model to catalyze the transfer of the γ-phosphate from

5   ATP to the Tyr OH.

The src:peptide substrate complex can now be used to model potential non-

peptide scaffolds and determine preferred substitution positions for the specificity

elements, all with an appropriately attached M_1 functionality, before choosing new

scaffolds to experimentally evaluate. The IRTK:peptide:AMP-PNP ternary structure

10   can also be used to model these potential scaffolds and preferred substitution

positions. These scaffolds have broad utility for the development of selective PTK

inhibitors by further developing them with appropriate specificity elements following

the strategy outlined in Figure 1.

The first non-peptide scaffold evaluated with this src:peptide substrate model

15   was the naphthalene scaffold. This is the first use of bicyclic aromatic scaffolds for

non-peptide PTK inhibitors, which do not compete with ATP. The naphthalene

scaffold's utility for this purpose was demonstrated by developing a non-peptide

inhibitor of the IRTK and EGF receptor PTK (Saperstein et al., 1989). The IRTK

ternary complexes were subsequently used to adapt this scaffold for src inhibition (see

20   Marsilje et al., 2000). The naphthalene scaffold was docked into the src active site by

first carrying out a least squares fitting of atoms *a-d* onto the peptide substrate as

indicated in Figure 6. In this way the naphthalene scaffold is related to the peptide

substrate by the cyclization shown by the arrow in Figure 6 and an appended OH as a

substitute for the substrate Tyr NH. This is essentially the same process used to dock

25   this scaffold into the IRTK structure as described in Marsilje 2000. The peptide

substrate was then deleted from the active site, various M_1 functional groups and

specificity elements S_2 & S_3 were then added to the scaffold as indicated and the

complexes were then individually minimized for 300 iterations. This same process

was also used to design the isoquinoline and indole scaffolds whose binding modes

30   are indicated in Figure 7.

In all of these modeled complexes selectivity element S_2 consists of various

hydrophobic side chains which can bind in the same pocket as the substrate P-1 Ile

side chain and selectivity element S_3 consists of various molecular fragments which

- 25 -

can bind in the P+1 to P+3 region of the peptide substrate binding sites (Figure 5). Since the active site region where M_1 binds is highly conserved among all of the protein kinases, the small menu of M_1 functional groups previously identified using peptide scaffolds served as the initial M_1 groups for attachment to the scaffolds at the

5   indicated positions. Of the two selectivity elements binding sites, the structure of the hydrophobic binding cavity for S_2 is known with greater confidence in the src model than is the P+1 to P+3 binding region for S_3. This is because the S_3 binding site was constructed partially by comparative homology modeling whereas the S_2 site is largely unchanged from the structure determined by x-ray for native src. In view of

10   these varied levels of confidence in the modeled binding sites for M_1, S_2 and S_3, the combinatorial library diversity is scaled such that the greatest variety and number of side chains in the combinatorial libraries are at the S_3 site followed by the S_2 site and then M_1.

The src results using M_1 functional groups to experimentally identify

15   promising non-peptide scaffolds are listed in Table 4. The data in Table 4 allows a number of conclusions to be drawn: 1) Low, but measurable, inhibition potency can be obtained with an appropriate M_1 group attached to a scaffold (e.g. __27__ & __38__). 2) 1 mM inhibitor concentrations for this type of screening is higher than desirable but 100 μM is too low. Screening of scaffolds bearing an M_1 group would optimally be

20   conducted at 500 μM. 3) The boronic acid, sulfamic acid and phosphonic acid M_1 functional groups, which had been identified using the PKA pentapeptide scaffold (__22__, Table 3 & __8__ Table 1) or the src pentapeptide scaffold (__14__, Table 2), respectively, give measurable activity when placed at the 2 position of the naphthalene ring (__27__, __28__ & __30__, respectively), the preferred position for M_1 identified in the model naphthalene

25   inhibitor:src complex (Figure 6). Moving the boronic acid or phosphonic acid M_1 groups to the 1 position (__32__ or __33__) reduced activity. 4) The related M_1 sulfonamide functionality, which was poor on the PKA pentapeptide scaffold (__7__ & __9__, Table 1) is also poor when appended to the 2 (__31__) or 1 (__34__) position of the naphthalene scaffold. The sulfonic acid analog at the naphthalene 2 position (__29__) is completely inactive,

30   even at 1mM. 5) The naphthalene scaffold can be replaced with a benzofuran (__35__) or a benzothiophene (__36__) scaffold without a noticeable reduction in activity when the boronic acid M_1 group is positioned analogous to the 2 position on a naphthalene. 6) The boronic acid M_1 group also provides active compounds when appended to the

- 26 -

isoquinoline (<u>37</u>) or indole (<u>38</u>) scaffolds at the positions indicated by modeling results (Figure 7). However, the indole scaffold is clearly favored over the isoquinoline scaffold suggesting that a hydrogen bond donating ability to Asn 468 (see Figure 7) is important for higher activity (this would require the protonated isoquinoline which is difavored by the adjacent electron withdrawing ester group). This conclusion is also supported by considering that a peptide substrate may position a hydrogen bond donating peptide bond NH at a similar position (Figure 6) and by finding that an equivalently positioned phenolic OH (Figure 6) improves potency (phenolic OH's are much better H-bond donors than acceptors) 8) When directly compared to other M_1 groups the boronic acid group is superior (e.g. <u>27</u> vs. <u>28</u>-<u>31</u>, <u>38</u> vs. <u>39</u>). 9) A biphenyl scaffold modeled into the src and IRTK active sites and found promising binding modes for this scaffold. Combinatorial libraries were developed with the biphenyl scaffold (see Pavia et al., 1996), and the modeling results were encouraging. Therefore, the para (<u>40</u>) and meta (<u>41</u>) isomers were evaluated with the boronic acid M_1 group. Both biphenyl compounds showed potency equivalent to the best naphthalene boronic acid (<u>27</u>) and therefore provide another scaffold geometry (the two phenyl rings are not planar) for further evaluation and development.

Since the bare scaffolds, with only an M_1 group appended, often have low binding affinity, the IC_{50}'s and K_i's for the 2-naphthalene boronic acid and sulfamic acid inhibitors were determined to ensure that a typical dose/response IC_{50} curve is obtained. This analysis provided the typical shape dose/response curves seen with more potent inhibitors. The IC_{50}'s and K_i's of these simple inhibitors also confirmed that the boronic acid inhibitor <u>27</u> is the more potent than the sulfamic acid analog <u>28</u> and has a K_i of about 554 μM.

The next issue addressed with these simple inhibitors before proceeding to elaborate them further was their mode of inhibition, specifically whether they are ATP-competitive inhibitors. In the case of the naphthalene inhibitors <u>27</u> & <u>28</u>, their IC_{50}'s were monitored as the ATP concentration was increased in three steps up to 1 mM. As a comparison, the IC_{50} of the pentapeptide phosphonic acid src inhibitor <u>14</u> (Table II) was also monitored. If any of these inhibitors were competing with ATP, then their IC_{50}'s should have increased proportionally with the ATP concentration (i.e. the dashed line). As shown, the IC_{50}'s for all three inhibitors remained essentially constant as the ATP concentration was increased demonstrating that they

- 27 -

are not ATP-competitive inhibitors. A very similar, but much less costly (commercial src is expensive), analysis was conducted with the indole boronic acid inhibitor __38__. In this case, the % inhibition was monitored with __38__ at a constant 500 μM inhibitor concentration but with increasing ATP concentrations of 200, 500 and 1,000 μM.

5   Once again the inhibitor potency was not reduced by the increasing ATP concentration demonstrating that _38_ is also non-ATP competitive.

The initial results obtained in Step 1 suggests that it is possible to identify promising scaffolds for further elaboration with this procedure. The biggest uncertainty with Step 1 is that some of the scaffolds identified in this way might not

10   be binding in the fashion suggested by the prior modeling evaluations. This is essentially a "false positive" problem. These "false positives" will likely fail in Step 2 , when they are evaluated for improved binding using the modeled complexes as a guide. Some false positive results can be accepted in Step 1 because the bare scaffolds with only the M_1 group attached are easily obtained. For further inhibitor

15   development, one may return to Step 1 each time new scaffolds are needed to carry through Steps 2 & 3. The best M_1 generated can be used each time Step 1 is repeated. Currently, the boronic acid M_1 group is preferred since it has a proven ability to give measurable activity with bare scaffolds. Also the boronic acid M_1 group offers multiple interesting possibilities for covalent and non-covalent interactions with the

20   conserved catalytic residues since it can: 1) hydrate, 2) form borate complexes with electron rich active site atoms, and/or 3) be phosphorylated and then react with active site nucleophiles or engage in additional non-covalent interactions. From the data in Table 4, the naphthalene and indole scaffolds were chosen as M_2 for the first efforts in Step 2 (the biphenyl scaffold is also a preferred scaffold). It is also worth mentioning

25   that naphthylalanine and analogs can be successfully substituted for the P 0 tyrosine · in src peptide substrates (e.g. see Alfaro-Lopez et al., 1998) further supporting the notion that naphthalene and related scaffolds can bind at the P 0 site.

TABLE IV

INITIAL STEP 1 RESULTS
% SRC INHIBITION IN CELLULAR MIMETIC ASSAY

Inhibitor	% Inhibition of 2 mM RR-src at Inhibitor Concentration ()	Inhibitor	% Inhibition of 2 mM RR-src at Inhibitor Concentration ()
M_1 (naphthalene)	... = Attaching bond.		
M_1		35	X=O 10 (100 µM)
27	59 (1 mM) 13 (100 µM) IC_{50}=950 µM K_i= 554 µM *NON-ATP COMPETITIVE*	36	X=S 12 (100 µM)
28	31 (1 mM) IC_{50}=1.6 mM K_i=963 µM *NON-ATP COMPETITIVE*	37	13 (500 µM)
29	0 (1 mM)		M_1
30	14 (1 mM)	38	*NON-ATP COMPETITIVE* 62 (500 µM)
31	0 (100 µM)	39	11 (500 µM)
M_1 (naphthalene)		40	13 (100 µM)
32	0 (100 µM)	41	14 (100 µM)
33	1 (1 mM)		
34	0 (100 µM)		

5   In comparing the naphthalene vs. indole scaffold results with a boronic acid M_1 group (i.e. 27 vs. 38, Table 4) the indole hydrogen bond donating NH and/or the adjacent ester group appeared to be the reason for the enhanced potency. Consequently, for Step 2 one of the first attempts was to add a hydroxyl group and an amide (with S_2) to the naphthalene scaffold at the adjacent positions suggested by the

10   modeling results (Figure 6). For the indole scaffold one priority was to prepare some amide analogs to see if potency can be increased with the S_2 specificity element

- 29 -

(Figure 7). In order to facilitate the synthesis of these initial analogs, an OH was temporarily substituted for the boronic acid M_1 group. The OH group is also known to interact with the catalytic residues, as required for an M_1 group, because it is the natural substrate M_1 whose phosphorylation rate is accelerated by interactions with

5   the catalytic residues. The results obtained for some of the initial analogs are given in Table 5 along with a side by side comparison, in the Cellular Mimetic src assay, to two literature src inhibitors **50** & **51** which are reported be non-ATP competitive. Some of these results and additional analogs are described in Marsilje 2000.

Inhibitor **50**, and analogs (Huang et al., 1995), were of particular interest

10   because the iminochromene scaffold is closely related to the naphthalene scaffold and it's binding mode would be expected to be very similar based upon the model (Figure 6). Partly because of this close analogy, the amides of hydroxyanilines with the naphthalene and indole scaffolds were examined as shown in Table 5. Also, the modeling studies with these hydroxyaniline amides derivatives in the src active site

15   indicated that the hydroxyl group may be able to engage in a hydrogen bonding interactions with the src Phe 424-Ala 422 backbone peptide bonds analogous to peptide substrates (see Figure 5). These modeling studies also indicated that the homologous hydroxybenzylamides should be active and, more importantly, provide a substitution position (i.e. the benzylic carbon) for appending side chains to bind in the

20   P-1 side chain pocket (e.g. to Arg 469, Figure 5).

The data in Table 5 allow the following conclusions to be drawn: 1) Adding an amide extension onto both the naphthalene and indole scaffolds can increase potency as predicted by the models for these scaffolds bound in the src active site (ca. 5-fold in the cases of **42** vs. **43**-meta & **47** vs **48**). 2) Adding a hydroxyl group to the

25   naphthalene scaffold adjacent to the amide increases potency (about 5-fold, **43**-meta vs. **44**) as predicted by the src model, and also suggests Asn 468 does hydrogen bond with this OH. 3) Moving the M_1 OH group from the position predicted to be best in the src model to the adjacent position reduces potency by one order of magnitude (**43**-meta to **45**). 4) The indole scaffold is less responsive than the naphthalene scaffold to

30   regiochemistry of the hydroxyaniline extension (**48** vs. **43**). 5) The naphthalene and the indole scaffolds accept the one carbon homologation provide by using hydroxybenzylamides (**46** vs. **43** & **49** vs. **48**). 6) The two M_1 hydroxy regioisomers of the naphthalene scaffold are both non-ATP competitive (see Marsilje 2000). 7) All

of the methyl hydroxyaniline and hydroxybenzylamide inhibitors were found to be less active suggesting that the hydroxyl group in the amide extension is functioning as a hydrogen bond donor. In this regard it is worth mentioning that in another src peptide substrate combinatorial library study Ser and Thr were identified as two of the

5   most preferred residues at the P+2 position (Alfaro-Lopez et al., 1998) suggesting that there are other binding opportunities for an amide extension OH other than to the Phe424-Ala 422 peptide bonds suggested by the modeling studies. 8) The most potent non-ATP competitive, non-peptide, src inhibitor previously disclosed in the literature (50) is not nearly as potent as reported when tested under the Cellular

10   Mimetic assay conditions (IC_{50}=118 nM reported by Huang et al., 1995 vs only 30% inhibition at 100 μM) and is less potent than a number of the current inhibitors (especially 43-meta) including the most analogous inhibitor (50 vs. 45). The structure-activity-relationship (SAR) reported for hydroxy regioisomers of 50 in their assay (Huang et al., 1995) also does not correspond with the SAR which was obtained

15 · for the related naphthalene inhibitors. For example, their iminochromene analog of the most potent naphthalene inhibitor 43-meta is 230-fold less potent than 50 in their src assay. An important advantage of the naphthalene scaffold over the iminochromene scaffold is that it allows a highly desirable S_2 specificity element to be added for accessing the P-1 hydrophobic site (see Figure 6) whereas the analogous

20   position can not be substituted on the iminochromene scaffold because it is occupied by the ring oxygen atom.

- 31 -

TABLE V
INITIAL STEP 2 RESULTS
% SRC INHIBITION IN CELLULAR MIMETIC ASSAY

Inhibitor		% Inhibition of 2 mM RR-src at Inhibitor Concentration ()	Inhibitor		% Inhibition of 2 mM RR-src at Inhibitor Concentration ()
42	(M₁)	47 (100 μM)	**47**	(M₁)	40 (500 μM)
43	(M₁) *NON-ATP COMPETITIVE*	Ortho: 39 (100 μM) Meta: 89 (100 μM) IC₅₀=18 μM, Kᵢ=10 μM Para: 23 (100 μM)	**48**	(M₁)	Ortho: 43 (100 μM) Meta: 30 (100 μM) Para: 45 (100 μM)
44	(M₁)	45 (100 μM)	**49**	(M₁)	Ortho: 24 (100 μM) Meta: In progress Para: 54 (100 μM)
45	(M₁) *NON-ATP COMPETITIVE*	51 (100 μM) IC₅₀=170 μM	**50**	(M₁?) Huang et al	30 (100 μM) Lit. IC₅₀= 118 nM
46	(M₁)	Ortho: 42 (100 μM) Meta: In progress Para: 42 (100 μM)	**51**	(M₁?) ST 638	37 (100 μM) Lit. IC₅₀=18 μM
			52	(M₁?) Piceatannol	41 (100 μM) Lit. IC₅₀ = 66 μM for p56[lck]

5   The inhibitor potencies in the src Cellular Mimetic assay can be further
calibrated against other literature non-ATP, non-peptide src inhibitors. Two additional
examples are **51** (ST 638, Shiraishi et al., 1989) which is a member of the
"tyrphostin" family of erbstatin analogs (see Lawrence & Niu, 1998) and the natural
product PTK inhibitor piceatannol **52** (Thakkar et al., 1993). In the Cellular Mimetic

- 32 -

assay all of these known inhibitors are less potent than had been reported suggesting that the assay is particularly demanding in terms of achieving high potency. The initial testing of src inhibitors is carried out using a single concentration (in triplicate) because commercial src is too expensive to do full IC_{50} curves on every inhibitor. It

5   should be mentioned, however, that an IC_{50} dose response curve is not linear and the difference between ca. 50% inhibition at 100 μM and a ca. 90% inhibition at 100 μM is actually a factor of 10 and not a factor of 2 (e.g. 45 vs. 43-meta). Consequently, the literature src inhibitors 50-52 are greater than an order-of-magnitude less active than the currently most potent inhibitor 43-meta.

10   The discrepancies found within the literature reporting the potency of these inhibitors, the sensitivity to assay conditions described earlier with the PKA inhibitors, and the lack of consistency among numerous labs and commercial protein kinase assay kits highlights this overlooked, but crucial, problem in the field. Although the inhibitors produced by the present invention may be more potent under

15   other assay conditions, the Cellular Mimetic assay should be used, which mimics the intracellular physical chemical conditions as closely as possible, as the primary potency and rank order guide for evaluating the inhibitors before choosing compounds to proceed to whole cell or tissue assays. As will be discussed in more detail later, the most potent naphthalene-based inhibitor thus far from the Cellular

20   Mimetic assay (i.e. 43-meta, IC_{50}=18 μM & K_i = 10 μM) is also effective in specifically blocking $pp60^{v-src}$ stimulated cell proliferation with a similar IC_{50} of ca. 25 μM. This suggests that not only is the Cellular Mimetic src assay predictive, but also that this class of naphthalene-based inhibitors can readily pass through cell membranes and inhibit intracellular src.

25   Analogs of a number of the naphthalene and indole inhibitors above can be prepared with the boronic acid M_1 group in place of the M_1 OH and/or with a S_2 hydrophobic specificity element attached for binding in the src P-1 site as illustrated in Figures 6 & 7. The naphthalene and indole scaffolds can then be taken through to Step 3 as described below. Each time Step 2 is repeated with new scaffolds from Step

30   1, the best selectivity elements S_2 and/or S_3 which have discovered with previous scaffolds will be used in the combinatorial libraries of Step 3. Even though the optimal combination of M_1, S_2 an S_3 is likely to be different for each scaffold, those

- 33 -

found optimal with the previous related scaffold (e.g. going from the naphthalene to the indole scaffold) should be suitable for utilization as better initial specificity elements in Step 2 with the new scaffold. The same process will be repeated each time there is a need to try another scaffold until sufficient potency, selectivity and

5   suitable pharmaceutical properties are achieved for the src inhibitors or, subsequently, for inhibitors of additional therapeutically important PTK's.

Some of the chemistry used to prepare the naphthalene inhibitors is described in Marsilje 2000. For attaching a boronic acid functionality in place of a M_1 hydroxyl groups in the src inhibitors from Table 5, the Pd (0)-catalyzed cross-coupling

10   methodology was used wherein either an aryl triflate (Ishiyama et al., 1997) or an aryl halide (Ishiyama, 1995) can be coupled with the commercially available pinacol ester of diboron. An illustrative example was have recently completed is given in Figure 8.

The example shown in Figure 8 demonstrates that it is possible to selectively triflate the less hindered OH at the M_1 position and have proven this by its removal to

15   **56** with subsquent ^{1}H NMR verification of the substitution pattern. The monotriflate **53** was then taken on to the desired boronic acid **55** as indicated. The same reaction sequence also works well for the regioisomer of **42** which corresponds to inhibitor **45** from Table 5. The synthetic scheme shown in Figure 9 can be followed, in order to attach hydrophobic S_2 selectivity elements to the naphthalene scaffold.

20   The naphthalene chemistry can be converted to the solid phase in preparation for synthesizing combinatorial libraries of this scaffold in a 96-well plate format. Thus far model chemistry has been carried out on the less active naphthalene regioisomer represented by **44** because this compound is readily obtained from commercially available 3,5-dihydroxy-2-naphthoic acid as describe in Marsilje 2000.

25   The successful model reactions to date are shown in Figure 10.

These model reactions demonstrate that it is possible couple the naphthalene scaffold to the Wang resin (**63**) and then carry out chemistry on the triflate [in this case the Pd (0)-catalyzed cross-coupling to the boronic ester **64**] followed by cleavage under mild conditions (**65**). The ester in **63** can also be saponified for subsequent

30   coupling reactions to form amides containing the S_3 selectivity elements.

The naphthalene scaffold currently provides three diversity sites to be explored in the combinatorial libraries, M_1, S_2 & S_3. Solid phase combinatorial chemistry with 96-well plate reactors similar to that used in previous studies (Pavia et

al., 1996). The greatest number and diversity of side chains will be used for S_3 followed by S_2 and then M_1 for the reasons discussed earlier. One possible overall synthetic strategy, based upon the synthetic model studies above, for preparing these libraries is shown in Figure 11.

Of course if problems arise with this route there are many other possibilities. For example, if the Mitsunobu coupling to give 67 proceeds in too low a yield (due to the increased steric congestion of the added adjacent allyl group-but perhaps not a problem given the 92% loading obtained in Figure 10) then the scaffold could be tethered to a resin through the carboxyl group, rather than the OH, using the acylsulfonamide "safety catch" linker (Backes et al., 1996) and form the amides last (the excess amines can be removed after cleavage by filtering through an acidic resin). Likewise, other linkers and/or resins can be used if the reduction of the alkene in the presence of benzylic ethers (67 to 68) is desired but problematic. The first use of the chemistry proposed in Figure 11 will be to simply prepare a library of 96 amides, containing the boronic acid M_1 group, without having the allyl side chain in place so that these two potential complications will not be a problem initially and the most promising S_3 elements can be quickly identified..

At least 14 S_2 hydrophobic side chains (includes linear, branched and cyclic) are identified for further study (28 if the corresponding alkenes are also explored) based upon the modeling of candidate side chains into the P-1 site of the src model (Figure 6) and on the commercial availability of the needed halides to prepare the corresponding Wittig reagents. At least 96 commercially available amines are available which will provide potential S_3 specificity elements including: 1) hydrocarbons (4), 2) alkyl groups containing hydrogen bond acceptors (4), 3) alkyl groups containing both hydrogen bond acceptors and donors (19), 4) alkyl/aryl groups containing hydrogen bond acceptors and donors (25), 5) aryl hydrogen bond acceptors and donors (10), 6) heterocyclic hydrogen bond acceptors and donors (20), 7) side chains containing cationic groups (4), 8) side chains containing anionic groups (9), and the 3-amino phenol side chain from inhibitor 43-meta as an internal control for src activity. A broad range of amines were included for S_3, in order not to overly bias the library here due to the higher level of uncertainty for this binding site in the src model.

- 35 -

The indole scaffold can be developed into a combinatorial library in much the same fashion. In this case, the indole NH would be used as the tether point for attachement to the Wang (or other) resin since the analogous Minsunobu reaction is known (Bhagwat & Gude, 1994). A large amount of synthetic methodology has been

5   developed for the synthesis of subsituted indoles and have designed a route to include the S_2 hydrophobic side chain (see Figure 7) (Ezquerra et al., 1996).

The triflate functionality formed in reaction 2 from intermediate <u>69</u> (Figure 11) can be converted to an amine (Wolfe et al., 1997) and then a series of amides or other amine derivatives following the reaction sequence shown in Figure 12. In fact,

10   the triflate is a versatile synthetic handle and could be converted into other functional groups as well.

When the amine <u>72</u> is available, the known M_1's (e.g. the sulfamic acid from src inhibitor <u>28</u> Table 5 and amide-acid <u>17</u> Table 3) can be evaluated with this more developed scaffold and evalulate some new amine derivatives as potential M_1's. For

15   example the hydrated tricarbonyl amide M_1 group shown in structure <u>73</u> (and it's non-hydrated precursor) is accessible via the synthetic methodology (see Lai et al., 1996) and could form a variety of interesting interactions with the conserved catalytic residues.

Following the modeling procedure described above, a the series of hydroxy-

20   containing analogs of the boronic acid M_1 group shown in Figure 13 were modeled in the src and IRTK active sites and found the illustrated interactions/binding modes as some of the interesting possibilities. By phosphorylating the boronic acid additional interesting possibilities are available (e.g. suicide type inhibition via reaction of the resulting mixed anhydride with an active site nucleophile). The presence of

25   additional hydroxyl groups on the Tyr-mimetic phenyl ring is necessary and common among many PTK inhibitors (e.g. Piceatannol <u>52</u>, Table 5) and was shown to be benefical on the side chain with the PKA phosphonate inhibitors (e.g. <u>2</u> vs. <u>3</u> and <u>4</u>, Table I). Consequently, adding one or more OH's to the boronic acid inhibitor M_1 design as illustrated in Figure 13 may considerably enhance potency. These OH

30   groups would also extend the boronic acid side chain past the catalytic Asp and Arg residues without suffering a penalty for covering them with hydrocarbon as was probably the case with the PKA boronic acid homologs (<u>23</u> & <u>24</u>, Table 3). One possible route to the hydroxyboronic acids <u>76</u> & <u>77</u> utilizes the chiral boronic ester

- 36 -

homologation methodology of Matteson (e.g. see Matteson et al., 1987, 1988 &
1990).

In a preferred embodiment of the invention, the first module is produced by
attaching the first module to a peptide scaffold. One or more functional groups are
5   identified which preferentially bind to catalytic residues of the protein kinase.
Further, the first module is combined with the second module so that the second
module substitutes for the peptide scaffold.

Preferred first modules have a functional group such as boronic acid, a
hydroxyl group, phosphonic acid, sulfamic acid, a guanidino group, carboxylic acid,
10   an aldehyde, an amide, and hydroxymethylphosphonic acid. The compounds of the
present invention may have two or more functional groups within the first module.
More preferred modules are boronic acid groups, a hydroxyl group, or an amide
group. An even more preferred amide group is a vicinal tricarbonyl amide.

Preferred second modules include indole, naphthalene, biphenyl, isoquinoline,
15   benzofuran, and benzothiophene. More preferred second modules are an indole or
naphthalene. In some embodiments of the invention more than one first module may
be bound to the second module. In addition, the first module may have a linear chain
comprising between one and three carbon atoms which links the first module to the
second module. In alternative embodiments, one of the carbon atoms in the linear
20   chain is substituted with a nitrogen, oxygen or sulfur atom.

The methods and compounds of the invention are broadly applicable to any
protein kinase. Preferred protein kinases are protein tyrosine kinases and protein
serine kinases. Preferred protein tyrosine kinases are $pp60^{c-src}$, $p56^{lck}$, ZAP kinase,
platelet derived growth factor receptor tyrosine kinase, Bcr-Abl, VEGF (vascular
25   endothelial growth factor) receptor tyrosine kinase, and epidermal growth factor
receptor tyrosine kinase, and epidermal growth factor receptor-like tyrosine kinases.
A more preferred protein tyrosine kinase is $pp60^{c-src}$. Preferred serine protein
kinases include MAP (mitogen activated protein) kinase, protein kinase C, and CDK
(cyclin dependent protein kinase).

30   The method of the present invention may further consist of adding one or
more specificity side chain elements to the combination of the first and second
modules. Specificity side chains can increase potency and specificity of the inhibitor.

- 37 -

Once a promising second module is identified it is not necessary to repeat all the steps of the method. Rather, the first module, specificity side chains, or a combination the two may be modified to improve the original inhibitor, i.e an inhibitor which has an increased ability to inhibit protein kinase activity when

5　compared to the unmodified first inhibitor.

The present method is designed to preferentially provide protein kinase inhibitors which do not act by inhibiting ATP binding t the protein kinase. Inhibitors of protein kinases may be potent but often lack specificity and are therefore often not good drug candidates. Therefore, protein kinase inhibitors which inhibit protein

10　kinase activity but does not inhibit or only weakly inhibit ATP binding to the protein kinase are preferred.

The present invention also provides a method for testing compounds for an ability to inhibit protein kinase activity. Compounds are produced according to claim 1. The activity of the protein kinase is measured in the presence of the inhibitor at the

15　same temperature, pH, ionic strength, osmolarity, and free magnesium concentration as found in a cell which expresses the protein kinase. The level of protein kinase activity is compared to the level of activity from the protein kinase without the presence of the inhibitor. Such an assay system which mimics physiological conditions provides the most relevant inhibition data. The assay may be conducted in

20　an automated assay system. Furthermore, the assay may be combined with a combinatorial chemistry method to rapidly screen numerous candidates.

The Pierce 96-well plate non-radioactive ELISA PTK assay method may be adapted to the Cellular Mimetic assay conditions for initial src screening of the 96-well plate combinatorial libraries. This high throughput assay utilizes the same RR-

25　SRC peptide substrate, except that it is biotinylated so that it can be attached to the NeutrAvidin-coated wells in their commercial 96-well plates. This high throughput inhibition assay can be run by incubating src with the RR-SRC substrate prebound to the wells followed by adding their anti-phosphotyrosine antibody (PY20)-horseradish peroxidase (HRP) conjugate and their HRP substrate to quantitate the level of

30　phospho-RR-SRC produced via measuring the level of HRP product with a 96-well plate UV reader. Standard low throughput P^{32}-ATP radioactive assays have been used, but a 96-well plate format is preferred, especially with a non-radioactive assay if possible. As very potent src inhibitors are developed, a panel of protein kinase assays

could be set up with up to ca. 6 commercially available protein kinases (mostly PTKs), using the Cellular Mimetic protein kinase assay conditions, and test these inhibitors across the panel to obtain an initial assessement of specificity. A more complete specificity assessment, involving the full ca. 2,000 protein kinases, will need

5   to be conducted in cell culture and in vivo through additional collaborations at the appropriate time.

Active src inhibitors can be studied in a set of side-by-side cell-based assays using normal rat kidney (NRK) cells and a temperature-sensitive $pp60^{v-src}$ tranformant of this cell line (LA25). The LA25 transformant engages in anchorage- and serum-

10 independent growth at the "permissive" temperature of 33°C due to activation of $pp60^{v-src}$ but not at the "non-permissive" temperature of 40°C at which $pp60^{v-src}$ is not activated (Li et al., 1996). The use of this pair of closely related cell lines for testing the src inhibitors at both the permissive and non-permissive temperatures allows one to determine if a given src inhibitor is blocking cell growth due to specific blockade

15 of the src signalling pathway, by a different mechanism or by a general cytotoxic effect. Results from initial testing of the non-peptide src inhibitor 43-meta (Table V) in this pair of cell lines are shown in Figure 14.

As shown in this graph the growth of the LA25 cells at the permissive temperature of 33°C is inhibited by ca. 50% at a 25 µM concentration of 43-meta

20 relative to the LA25 cell growth at the non-permissive 40°C as a control. The lack of cell toxicity of 43-meta is evidenced by the fact that as its concentration is increased up to 400 µM, the basel growth of the NRK non-transformed cells, the LA25 cells at the non-permissive 40°C and the LA20 cells at the permissive temperature of 33°C (but with $pp60^{v-src}$ fully inhibited by 43-meta) not only does not decrease but actually

25 increases somewhat (presumably due to a non-src related activity of this compound). Since the 43-meta solutions were prepared with a low concentration of DMSO for solubilization a DMSO control was also run at the same concentration. A more complete dose/response curve centered around 25 µM will be run.

In another embodiment, the present invention provides a method of inhibiting

30 a protein kinase. The protein kinase is contacted with a compound having a first module which has a functionality for binding to catalytic residues of the protein

kinase and a second module which provides a non-peptide scaffold. The combination
of the first and second modules inhibits the protein kinase activity.

A preferred non-peptide protein tyrosine kinase inhibitor provided by the
present invention has the following formula:

5

10   wherein R1 is H or OH, R2 is H or OH, R3 is OH or H, and R4 is CH_3, $CH_2(CH_3)R$,
or $CH_2(CH_3)S$, R5 is OCH_3, H, or OH, R6 is OCH_3, F, H, or OH, and R7 is OCH_3, H,
OH, CO_2H, CO_2CH_3, CH_2CO_2H, or $CH_2CO_2CH_3$. In a more preferred embodiment,
the non-peptide protein tyrosine kinase inhibitor inhibits the activity of $pp60^{c-src}$
tyrosine kinase.

15   Another preferred non-peptide protein tyrosine kinase inhibitor has the
following formula:

20

where R1 is OH or H, R2 is OH or H, R3 is OH or H, R4 is OH or H, R5 is OH, OMe,
or H, R6 is OH, OMe, or H, R7 is OH, OMe, or H, and X is 0 or 1. In a more
preferred embodiment, the non-peptide protein tyrosine kinase inhibitor has the above

25   structure and R1 is OH, R2 is OH, R3 is H, R4 is H, R5 is OMe, R6 is H, R7 is H, and
X is 1.

Yet another preferred non-peptide protein tyrosine kinase has the formula:

30

- 40 -

The present invention further provides a method of treating a condition, responsive to a protein kinase inhibitor, in a patient. An effective dose of a protein kinase inhibitor is administered to a patient. The protein kinase inhibitor has a first module having a functionality for binding to catalytic residues of the protein kinase

5   and a second module which provides a non-peptide scaffold, where the combination of the first and second modules inhibits protein kinase activity.

Finally, promising src inhibitors can be screened in primary human tumor tissue assays, particularly to look for synergy with other known anti-cancer drugs.

10   **EXAMPLES**

**Example 1 -   Design, Synthesis and Activity of Non-Atp Competitive
               Hydroxynaphthalene Derivative Inhibitors of pp60$^{c\text{-}Src}$ Tyrosine
               Kinase**

15

The crystal structure of the autoinhibited human IRTK catalytic domain (Hubbard et al.., 1994) was used to carry out qualitative molecular modeling studies (SYBYL™, 6.4, Tripos Inc., St. Louis) wherein a naphthalene ring was superimposed upon the IRTK Tyr 1,162. The IRTK region containing Tyr 1,162 folds back into the

20   active site, with Tyr 1,162 positioned analogous to a phosphorylatable Tyr in a peptide substrate, thereby autoinhibiting the tyrosine kinase. This superimposition indicated that an amide carbonyl should be placed at the 2-position (Scheme 1) of the

Scheme 1

25   naphthalene ring to mimic the Tyr 1,162 carbonyl and a hydroxyl group should be positioned at the 6-position to mimic the Tyr 1,162 hydroxyl group. These modeling studies also indicated that a hydroxyl group at the 3-position could mimic the Tyr 1,162 NH.

In order to test these design concepts experimentally, the 2-position carbonyl group was appended as either a methyl ester or as a series of amides (Table 6). The hydroxy N-phenyl (X=0) and N-benzyl (X=1) amides were chosen based upon the increase in pp60[c-src] inhibitor potency observed with iminochromene analogs

5   containing appended hydroxy N-phenyl amide side-chains (Huang et al., 1995). Analogs wherein the 6-hydroxyl group was either deleted or moved were also prepared to determine if a drop in potency occurs as predicted from the modeling studies.

The series of 2-carbonyl-3,5-dihydroxy naphthalene inhibitors (**1a, 2a-2d, 2i-**

10   **2l, 2o-2p**) and 2-carbonyl-3,7-dihydroxy naphthalene inhibitors (**1c, 2t-2u**) were synthesized from commercially available (Aldrich) 3,5-dihydroxy-2-naphthoic acid and 3,7-dihydroxy-2-naphthoic acid, respectively. The methyl esters **1a** and **1c** were obtained by refluxing the respective acid starting materials for 48h in methanol pre-saturated with HCl gas. The amides (**2a-2d, 2i-2l, 2o-2p, 2t-2u**) were synthesized by

15   coupling the respective carboxylic acid with commercially available (Aldrich or Lancaster) amines using one of two methods. The first method utilized the NBS/PPh$_3$ methodology as described by Froyen (Froyen, 1997). The second method utilized IIDQ (Aldrich) as the coupling reagent. The carboxylic acid was first reacted with 1.0 eq. IIDQ in anhydrous DMF at room temperature for 24h. The respective amine (2.0

20   eq.) was then added neat and the reaction was heated to 80°C for 2-6 hours. After aqueous workup, purification was achieved by silica gel chromatography and precipitation from CH$_2$Cl$_2$/hexane, followed by preparative C-18 RP-HPLC (CH$_3$CN/H$_2$O), if necessary. The benzyl amines were commercially available only as their corresponding hydroxyl protected methyl ethers. Consequently, after amide

25   formation, the hydroxyl groups were deprotected by treatment with 6 eq. BBr$_3$ in DCM for 1 minute at -78°C followed by 1 hour at room temperature.

- 42 -

Table 6: pp60[c-src] inhibitory activity of hydroxynaphthalene derivatives and select

published inhibitors.[a,b,c]

| Compd	R1	R2	R3	R4	R5	R6	R7	X	% Inhibition at 100 μM (std. dev.)	IC50 (μM)
1a	OH	OH	H	H	N/A	N/A	N/A	N/A	5 (+/-2)	n.t.
1b	OH	H	OH	H	N/A	N/A	N/A	N/A	47 (+/-3)	n.t.
1c	OH	H	H	OH	N/A	N/A	N/A	N/A	19 (+/-6)	n.t.
1d	NH₂	H	H	H	N/A	N/A	N/A	N/A	inactive	n.t.
2a	OH	OH	H	H	OH	H	H	0	12 (+/-4)	n.t.
2b	OH	OH	H	H	H	OH	H	0	51 (+/-1)	150
2c	OH	OH	H	H	H	H	OH	0	60 (+/-7)	n.t.
2d	OH	OH	H	H	OH	H	OH	0	14 (+/-2)	n.t.
2e	OH	H	OH	H	OH	H	H	0	39 (+/-5)	n.t.
2f	OH	H	OH	H	H	OH	H	0	89 (+/-1)	16
2g	OH	H	OH	H	H	H	OH	0	23 (+/-5)	n.t.
2h	OH	H	OH	H	OH	H	OH	0	56 (+/-1)	n.t.
2i	OH	OH	H	H	H	OMe	H	0	33 (+/-5)	n.t.
2j	OH	OH	H	H	H	H	OMe	0	35 (+/-8)	n.t.
2k	OH	OH	H	H	OMe	H	H	1	13 (+/-3)	n.t.
2l	OH	OH	H	H	H	H	OMe	1	14 (+/-2)	n.t.
2m	OH	H	OH	H	OMe	H	H	1	inactive	n.t.
2n	OH	H	OH	H	H	H	OMe	1	4 (+/-7)	n.t.
2o	OH	OH	H	H	OH	H	H	1	41 (+/-2)	n.t.
2p	OH	OH	H	H	H	H	OH	1	49 (+/-4)	n.t.
2q	OH	H	OH	H	OH	H	H	1	42 (+/-2)	n.t.
2r	OH	H	OH	H	H	OH	H	1	55 (+/-3)	n.t.
2s	OH	H	OH	H	H	H	OH	1	42 (+/-3)	n.t.
2t	OH	H	H	OH	H	OH	H	0	68 (+/-5)	n.t.
2u	OH	H	H	OH	H	OH	H	1	40 (+/-3)	n.t.
2v	H	H	OH	H	H	OH	H	0	45 (+/-5)	n.t.
Iminochromene 9TA									30 (+/-15)	Lit[8]: 0.118
Piceatannol									41 (+/-2)	Lit[13]: 66 (lck)
ST-638									37 (+/-5)	Lit[14]: 18
Emodin[d]									22 (+/-3)	Lit[15]: 38
Tyrophostin A47									43 (+/-3)	

Table 6 Footnotes:

[a] The previously described assay procedure (Lai et al., 1998) was used with the
following assay components, final concentrations and conditions: 50.0 mM MOPS,
4.02 mM MgCl$_2$, 6.00 mM K$_3$citrate (used as a Mg^{2+} buffer to stabilize the *free* Mg^{2+}
at 0.5 mM), 99.0 mM KCl, 10.0 mM 2-mercaptoethanol, 198 µM ATP, 19.8 µM
ADP, 10 U full length human purified recombinant pp60^{c-src} (Upstate Biotechnology
Inc.), 2.00 mM RR-SRC, 4.0 % DMSO, pH 7.2, 37°C. These overall assay conditions
have been shown (Choi, 1999) to reproduce the intracellular conditions of pH, temp.,
free Mg^{2+} (0.5 mM), ionic strength, osmolality, ATP/ADP and reduction potential.
[b] All new compounds were characterized by proton NMR, EI or FAB(+) MS and are
pure by TLC.
[c] N/A = Not applicable, n.t. = Not tested.
[d] ATP-competitive.

The series of 2-carbonyl, 3,6-dihydroxy naphthalene inhibitors (**1b, 2e-2h,
2m-2n, 2q-2s**) were synthesized from 3,6-dihydroxy-2-naphthoic acid **6** using the
methods described above. The synthesis of intermediate **6** that was developed is
shown in Scheme 2 beginning with commercially available 2,7-dihydroxynaphthalene
3 (Aldrich).

Compound **1d** was synthesized from 3-amino-2-naphthoic acid (Aldrich) by
reaction with TMS-diazomethane in DCM at room temperature. Compound **2v** was
synthesized from 6-hydroxy-2-naphthoic acid (Aldrich) using the amidation method
described by Froyen (Froyen, 1997).

- 44 -

Kinase assay conditions have been shown to influence the measured inhibitory activity (Lawrence et al., 1998). Consequently, in order to accurately determine the relative potency of the newly designed class of pp60$^{c\text{-src}}$ inhibitors, the inhibitory activity of four previously published, non-ATP competitive PTK inhibitors, was also

5   tested. Piceatannol, ST-638, and Tyrphostin A47 were chosen because they are commercially available (Sigma or Calbiochem), and are representative of the spectrum of known non-ATP competitive PTK inhibitors. Emodin (Calbiochem) is ATP-competitive when analyzed with the tyrosine kinase p56^{lck}. Previously, iminochromene 9TA was the most potent non-ATP competitive pp60$^{c\text{-src}}$ inhibitor

10   reported (Huang et al., 1995). Since iminochromene 9TA was not commercially available, it was synthesized using a novel route by converting 3-Aminophenol to the corresponding TBDMS ether (1.1 eq. TBDMS-Cl, 1.1 eq. DIEA, 5 mol% DMAP, DMF, 24 h, rt, 71%). The resulting aniline was coupled using 2.0 eq. of cyanoacetic acid (1.1 eq. EDCI, 1.1 eq. TEA, DMF, 18 h, 75°C, 70%). Condensation of the

15   resulting amide with 1.2 eq. of 2,3-dihydroxybenzaldehyde (cat. piperidine, abs. EtOH, 2 h, 60°C) followed by deprotection (1.1 eq. TBAF, THF, 15 m, 43% overall) gave iminochromene 9TA with satisfactory elemental, FAB(+)MS and ^{1}H NMR analysis after purification by flash chromatography (10:1, DCM:MeOH).

The inhibitory activities shown in Table 6 for compounds **1a-d** and **2a-2v**

20   were determined using purified, full length, human recombinant pp60$^{c\text{-src}}$. Due to the number of compounds tested, and the associated cost, their rank order potencies were first determined at a constant inhibitor concentration (100 μM). As predicted by the modeling studies, based upon analogy to the IRTK Tyr 1,162 hydroxyl group, a preference for positioning the naphthalene hydroxyl group on carbon 6 vs. 5 or 7 was

25   observed in both the ester (**1b**, 47% vs. **1a**, 5% & **1c**, 19%) and amide (e.g. **2f**, 89% vs. **2b**, 51% & **2t**, 68%) series. The prediction that attaching a hydroxyl group at naphthalene carbon 3 (mimicking the Tyr 1,162 NH) would improve potency was also confirmed (**2f**, 89% vs. **2v**, 45%). Finally, the prediction that extending the inhibitor as an amide at the 2 position (mimicking the peptide bond) could further improve

30   potency was confirmed as well (e.g. **2f**, 89% vs. **1b**, 47%).

-45-

The data provided in Table 6 demonstrate that moving the hydroxyl group from the optimal 6 position to the adjacent naphthalene carbon 5 results in a different structure activity profile with regard to the optimal concurrent positioning of the hydroxyl group(s) in the amide side chain (e.g. **2f/2g** vs. **2b/2c**). Also of note is the

5   replacement of the amide side chain hydroxyl group with a corresponding methoxy group in compounds **2i-2n**. In the case of the N-phenyl amides (**2i-2j**), their activity, relative to the corresponding hydroxy amides (**2b-2c**), was not reduced as significantly as in the case of the N-benzyl amides (**2k-2n** vs. **2o-2q, 2s**). This suggests that in the benzyl derivatives, the amide side chain hydroxyl groups either

10   interact with the enzyme as hydrogen bond donors, or the methoxy groups are too large to fit in the binding site.

A more quantitative analysis of the selectivity for positioning a hydroxyl group on carbon 6 vs. 5 is provided by comparing the IC_{50}'s of **2f** (16 μM) vs. **2b** (150 μM), respectively. These results also confirm that a drop in % inhibition from

15   ca. 90% to ca. 50% represents an order of magnitude difference in potency, as expected. Similarly, a drop in % inhibition from ca. 50% to 10% would represent another order of magnitude difference in potency.

A direct comparison of the most potent inhibitor from this series, compound **2f**, with the five previously reported PTK inhibitors shown in Table 6 demonstrates

20   that, under these assay conditions, **2f** is more potent by one to two orders of magnitude. Interestingly, iminochromene 9TA was previously reported (Huang et al., 1995) to have an IC_{50} of 118 nM against $pp60^{c-src}$, and was the most potent known non-ATP competitive $pp60^{c-src}$ inhibitor, but under the current assay conditions only a 30% inhibition at 100 μM was observed. These results re-emphasize (Lawrence et

25   al., 1998) the importance of comparing protein kinase inhibitors under identical assay conditions.

A goal of these studies was to obtain non-peptide $pp60^{c-src}$ inhibitors which do not compete with ATP. Consequently the % inhibition of $pp60^{c-src}$ by **2f** and **2b** at constant inhibitor concentrations was monitored as a function of increasing [ATP] up

30   to a cellular mimetic 1 mM level. Since the [ATP] had little effect on the %

- 46 -

inhibition, both 2f and 2b are non-competitive inhibitors with respect to ATP. The %

inhibition was measured using ATP concentrations of 200, 500 & 1,000 μM while

holding the inhibitor concentration constant. If the inhibitor is directly competing with

ATP, then this 5-fold overall increase in [ATP] is equivalent to decreasing the

5   inhibitor concentration 5-fold in terms of the effect on % inhibition. Consequently the

% inhibition should decrease to the value observed in the IC_{50} dose-response curve

(obtained with 200 μM ATP) for 1/5 of the set inhibitor concentration used in this

experiment if direct competition with ATP is occurring. For inhibitor 2f (set at 25

μM) a 62% (+/-5), 54% (+/-3) and 50% (+/-1) inhibition at 200 μM, 500 μM and

10   1,000 μM ATP, respectively, was obtained whereas the level of inhibition should

have dropped to ca. 20% at 1,000 μM ATP if direct competition with ATP were

occurring. Similarly, for inhibitor 2b (set at 300 μM) an 84% (+/-1), 81% (+/-1) and

77% (+/-2) inhibition at 200 μM, 500 μM and 1,000 μM ATP, respectively, was

obtained.   The high cost of many kinases has stimulated other researchers to monitor

15   inhibitor potency as a function of increasing [ATP] for the same purpose (Saperstein

et al., 1989; Burke et al., 1993; Davis et al., 1989; Davis et al., 1992; Faltynek et al.,

1995; and Sawutz et al., 1996).

In summary, structure-based design has produced a series of

hydroxynaphthalene pp60[c-src] non-peptide inhibitors that do not compete with ATP.

20   Results with compounds from this series in cell-based assays, as well as detailed

kinetic studies under various assay conditions, will be reported in due course. An

extension of these design concepts from the naphthalene scaffold to an indole scaffold

is reported in the following paper.

25 ⁄   **Example 2 - Design, Synthesis and Activity of Non-ATP Competitive**
         Hydroxyindole Derivative Inhibitors of pp60[c-Src] Tyrosine Kinase

In the preceding example, the structure-based design of a series of pp60[c-src]

inhibitors utilizing a naphthalene scaffold is described. These compounds were

30   designed to bind in the peptide substrate site because of the potential for greater

selectivity and efficacy in a cellular environment relative to the alternative ATP

Scheme 1

substrate site. This example presents an extension of these design concepts to a series

5   of pp60^{c-src} inhibitors based upon an indole scaffold. Once again the crystal structure

of the autoinhibited insulin receptor PTK (IRTK) was used to carry out qualitative

molecular modeling studies, except in this case an indole ring was superimposed upon

the IRTK Tyr 1,162. This superimposition indicated that the indole NH can mimic

the Tyr 1,162 NH, that a carbonyl should be placed at the 2-position, and a hydroxyl

10   group at the 5 position to mimic the Tyr 1,162 carbonyl and OH, respectively

(Scheme 1). The conceptual cyclization of Tyr 1,162 to the smaller 5-membered ring

of an indole illustrated in Scheme 1, relative to a 6-membered ring in the case of the

naphthalene scaffold (Karni et al., 1999), results in a movement of the optimal

positioning of the OH from carbon 6 in the naphthalene scaffold to carbon 5 in the

15   indole scaffold.

The indole amide derivatives containing hydroxy phenyl/benzyl side chains

2d-f, 2j-l (Table 7), respectively, were selected based upon the increase in pp60^{c-src}

inhibitor potency observed for the analogous naphthalene-based hydroxy phenyl

amides reported in the previous example. The corresponding methyl ethers **2a-c,g-i,v**

20   are precursors in the synthesis. The additional analogs shown in Table 7 were

prepared to begin expanding the range of side chains beyond the hydroxy/methoxy

groups that have now been extensively probed with both the indole and naphthalene

scaffolds.

The indole amides containing only hydroxy or methoxy side chains were

25   synthesized as illustrated:

- 48 -

Scheme 2

The 2-indolecarboxylic acid derivative, the methoxyphenyl amine (1.1 eq, Aldrich, Lancaster or Fluka), and the coupling reagent PyBOP (benzotriazol-1-

5   yloxy)tripyrrolidino-phosphonium-hexafluorophosphate) (1 eq, Fluka) were dissolved in anhydrous DMF. The solution was cooled to 0°C under argon and then diisopropylethylamine (DIEA, 3 eq) was added. The reaction was stirred at 0°C for 1m followed by 1 hour at room temperature. After workup the residue was purified by silica gel chromatography.

10   The methyl ethers were cleaved with boron tribromide (1 M in DCM, Aldrich) when desired. The indole amide methyl ether was suspended in dry DCM and cooled to -78°C under argon. One equivalent of BBr_3 was added for each heteroatom in the starting material plus one excess equivalent. The resulting dark red solution was stirred at -78° for 30m and then at room temperature for 1-2 hours. The reaction was

15   quenched with water (10 minutes) before workup.

Table 7: pp60[c-src] inhibitory activity of hydroxyindole derivatives.[a,b,c]

1a-1b   **2a-2z**

Compd	R1	R2	R3	R4	R5	R6	R7	% Inhibition at 100 μM (std. dev.)
1a	H	OH	H	CH_3	N/A	N/A	N/A	40 (+/-5) [at 500 μM]
1b	H	OH	OH	CH_2CH_3	N/A	N/A	N/A	28 (+/-3)
2a	H	OH	H	--	OCH_3	H	H	3 (+/-1)
2b	H	OH	H	--	H	OCH_3	H	21 (+/-2)
2c	H	OH	H	--	H	H	OCH_3	39 (+/-9)
2d	H	OH	H	--	OH	H	H	43 (+/-1)
2e	H	OH	H	--	H	OH	H	30 (+/-6)
2f	H	OH	H	--	H	H	OH	45 (+/-3)
2g	H	OH	H	CH_2	OCH_3	H	H	21 (+/-5)
2h	H	OH	H	CH_2	H	OCH_3	H	7 (+/-6)
2i	H	OH	H	CH_2	H	H	OCH_3	18(+/-4)
2j	H	OH	H	CH_2	OH	H	H	24(+/-3)
2k	H	OH	H	CH_2	H	OH	H	74(+/-2) [IC_{50} = 38 μM]
2l	H	OH	H	CH_2	H	H	OH	54(+/-2)
2m	H	OH	H	CH_2CH_2	H	H	OH	21(+/-7)
2n	H	OH	H	CH_2	H	H	CO_2H	not active
2o	H	OH	H	CH_2	H	H	CO_2CH_3	11(+/-4)
2p	H	OH	H	--	H	H	CH_2CO_2H	7(+/-6)
2q	H	OH	H	--	H	H	$CH_2CO_2CH_3$	32(+/-7)
2r	H	OH	H	--	H	F	H	21(+/-7)
2s	H	OH	H	CH_2	H	F	H	57(+/-6)
2t	H	OH	OH	CH_2	H	OH	H	26(+/-2)
2u	H	H	OH	CH_2	H	OH	H	56(+/-6)
2v	H	H	H	CH_2	H	H	OCH_3	4(+/-4)
2w	H	H	H	CH_2	H	H	OH	36(+/-4)
2x	OH	H	H	CH_2	H	OH	H	60 (+/-3)
2y	H	OH	H	$CH(CH_3)$ R	H	OH	H	15(+/-3)
2z	H	OH	H	$CH(CH_3)$ S	H	OH	H	13(+/-7)

[a] All compounds were tested as described in the preceding paper.[5]

[b] All compounds were characterized by proton NMR, FAB(+) MS and are pure by TLC.

[c] N/A = Not applicable.

Using this synthetic route, the series of 5-hydroxyindole amide inhibitors 2a-m,y,z were prepared from 5-hydroxy-2-indolecarboxylic acid. The 4- and 6-hydroxyindole amides (2x,u, respectively) were synthesized from methyl 4-methoxy-

- 50 -

2-indolecarboxylate and methyl 6-methoxy-2-indolecarboxylate, respectively. The 5,6-dihydroxyindole amide 2t was prepared from ethyl 5,6-dimethoxyindole-2-carboxylate. Sonication of the esters in 1 N NaOH for 1h provided the corresponding carboxylic acids for coupling. The des-hydroxy indole amides 2v,w were synthesized from indole-2-carboxylic acid. All of the indole starting materials were commercially available (Aldrich or Lancaster).

The fluoro inhibitors 2r,s were likewise prepared from the corresponding fluorophenyl amines (Aldrich). The inhibitors containing esters or carboxylic acids on the amide side chain, 2n-q, were prepared from the corresponding amino carboxylic acids (Aldrich). The side chain carboxylic acid was first protected as a methyl ester (anh. MeOH pre-saturated with HCl, reflux, 1d), followed by PyBOP coupling (as above), then saponification back to the carboxylic acid when desired.

The methyl ester 1a was prepared by refluxing a solution of the carboxylic acid overnight in anhydrous methanol pre-saturated with HCl gas. The ethyl ester 1b was prepared by BBr_3 deprotection of ethyl 5,6-dimethoxyindole-2-carboxylate as above. All of the inhibitors listed in Table 7 were purified by silica gel chromatography.

As in Marsilje 2000, the rank order activity of this series of pp60[c-src] inhibitors was first determined at a constant inhibitor concentration (Table 7). The same inhibitor concentration (100 μM) was used for the current indole series of inhibitors, the previous naphthalene series of inhibitors, and five non-ATP competitive literature PTK inhibitors (see preceding paper). This allowed an efficient rank order comparison of 59 compounds in total under identical assay conditions.

The modeling studies predicted that a hydroxy group at carbon 5 of the indole scaffold would be optimal. Comparison of the 5-hydroxy indole inhibitor 2k (74%) with the analogous 6-hydroxy indole inhibitor 2u (56%) and 4-hydroxy indole inhibitor 2x (60%) confirms this prediction, although the preference is not strong. The prediction that a hydroxy group at carbon 5 will improve the activity (relative to no hydroxy group) is confirmed by comparing the 5-hydroxy indole inhibitor 2l (54%) with the corresponding des-hydroxy inhibitor 2w (36%).

- 51 -

Extending the indole inhibitors as aryl amides at carbon 2 improved potency, as expected based upon the previous naphthalene inhibitors. For example, the meta-hydroxybenzyl amide indole 2k gives 74% inhibition at 100 μM whereas the analogous methyl ester 1a gives only 40% inhibition at 500 μM. Interestingly,

5   comparing the 5,6-dihydroxy ethyl ester 1b (28%) to the corresponding aryl amide 2t (26%) shows that the simultaneous presence of the second hydroxy at carbon 6 prevents the potency enhancement normally provided by the otherwise preferred meta-hydroxybenzyl amide side chain. This amide side chain was the best of the current series when the 5-hydroxyl group is present alone (2k, 74%) and still gave

10   good inhibition when a 6-hydroxy group was present alone (2u, 56%). Also, the simultaneous presence of two hydroxy groups at carbons 5 & 6 seems well tolerated in the absence of an amide side chain (1b vs. 1a & 2e). This data suggests that a change in the binding orientation of the indole scaffold may have occurred due to the presence of the second hydroxy group and that a different amide side chain may now

15   be preferred. The optimal combination of side chains at carbons 4-7 (including functional group replacements for hydroxy groups (Lai et al., 1999)) and amide side chains is currently under investigation.

In general, the indole scaffold structure-activity-relationships ("SARs") revealed by the data in Table 7 parallels that reported in the preceding paper for the

20   naphthalene scaffold. In both cases positioning a hydroxy group on the scaffold analogous to the Tyr 1,162 OH, as identified by modeling studies, provided the highest potency. Moving this hydroxy group to one of the adjacent carbons reduced the potency, but not dramatically, in both cases. Extending both scaffolds with aryl amides at the position identified by the modeling studies to mimic the Tyr 1,162

25   peptide bond improved the potency. With both scaffolds, substitution of a methoxy group for the hydroxy groups on the amide side chain usually reduced potency, and did so to a greater extent with the longer benzylamide side chain (e.g. 2k, 74% vs. 2h, 7% compared to 2e, 30% vs. 2b, 21%). The major difference in the SARs for these two scaffolds is that the 5-hydroxyindole scaffold prefers the longer m-hydroxybenzyl

30   amide side chain (2k, 74% vs. 2e, 30%) whereas the analogous 3,6-dihydroxynaphthalene scaffold prefers the shorter amide side chain derived from m-

- 52 -

hydroxyaniline. The 5-hydroxyindole scaffold showed essentially no preference for

the position of the hydroxyl group on the shorter amide side chain (**2d-f**) whereas with

the longer hydroxybenzyl amide side chain a significant preference for the meta

position was observed (**2j-l**). In the case of the 3,6-dihydroxynaphthalene scaffold the

5   opposite was observed.

Additional molecular modeling studies were carried out to further probe the

preference for a longer amide side chain with the indole scaffold. The most active

naphthalene inhibitor **3** from the previous report was used as a template upon which

the analogous indole inhibitor **2e** and the homologated indole inhibitor **2k** were

10   superimposed. The three most important side chain functional groups in naphthalene

inhibitor **3** are considered to be the 6-hydroxy group (H-bond donor and acceptor), the

Scheme 3

hydrogen from the 3-hydroxy group (H-bond donor), and the side chain hydroxy

15   group (H-bond acceptor) based upon the rational design and SAR for both series of

inhibitors. This three point pharmacophore model is identified in both series by

asterisks in Scheme 3.

The "multifit", energy minimization and "fit atoms" facilities within

SYBYL™ (6.4, Tripos, St. Louis) were used in sequence to superimpose **2e** and **2k**

20   onto **3**. This overall fitting process was carried out with spring constants (multifit)

and weights (fit atoms) chosen such that the highest emphasis was on optimally

superimposing the scaffold pharmacophore O's and H's (100), followed by the side

chain O's (10) and then the intervening amide bond (1). The "multifit" process

adjusted the conformations for maximum pharmacophore fit, the subsequent

25   minimization produced the nearest local minimum energy conformations and finally

the "fit atoms" process produced the best pharmacophore superimposition of these

- 53 -

minimized conformations. As expected, the scaffold pharmacophore O's and H's of both **2e** and **2k** superimposed closely and similarly upon the corresponding atoms in **3** (all within ca. 0.50 A°). However, the side chain pharmacophore O's of **2e** and **2k** differed significantly in their superimposition on the corresponding O of **3**, with

5   displacements of 1.8 A° vs. only 0.08 A° respectively. This close fit of the three key pharmacophore sites between **2k** and **3** provides a rationalization for their potency differing by only a factor of 2.4 (IC_{50}'s 38 μM vs. 16 μM, respectively).

Extending the amide side chain by another carbon atom reduced the activity (**2m**, 21% vs. **2l**, 54%). Adding a methyl group to the benzylic carbon of **2k**, in either

10   stereochemistry, greatly reduced the activity (**2y**, 15% & **2z**, 13% vs. **2k**, 74%). Replacing the side chain hydroxy group (in the para position) with a carboxylate anion (**2n**, 0% vs. **2l**, 54% and **2p**, 7% vs. **2f**, 45%) reduced the activity whereas the corresponding methyl esters (**2o**, 11% & **2q**, 32%, respectively) showed a smaller loss of potency. Importantly, replacing the side chain hydroxy group with a fluorine

15   maintained much of the potency (**2s**, 57% vs. **2k**, 74% and **2r**, 21% vs. **2e**, 30%). Consequently, the fluoro analog **2s** has only one hydroxy group left for potential Phase II metabolism (e.g. glucuronide formation), and this remaining hydroxy group is a current target for replacement (Lai et al., 1998).

Using the same method as in the preceding example (Marsilje2000), the most

20   potent inhibitor from the current indole series (**2k**) was analyzed for ATP competition by monitoring the % inhibition at increasing [ATP] while holding the inhibitor concentration constant. Since the [ATP] had little effect on the % inhibition (The % inhibition was 46% and 41% with **2k** at 45 μM and [ATP] at 200 μM or 1,000 μM, respectively.), **2k** is non-competitive with respect to ATP under these assay

25   conditions.

In summary, an indole scaffold has been designed, and an initial SAR carried out, for the development of non-ATP competitive pp60^{c-src} inhibitors. The potency of the best indole-based inhibitor from the current series was found to be close to that of the best naphthalene-based inhibitor. The % inhibition was 46% and 41% with **2k** at

30   45 μM and [ATP] at 200 μM or 1,000 μM, respectively.

- 54 -

Example 3 - Synthesis of Indole Derivative Protein Kinase Inhibitors

The following results show the synthesis and testing of indole derived protein kinase inhibitors. Four reaction schemes are provided and separately followed by experimental details for the preparation of the final product of each of these reaction schemes. These final products are examples of indole-base tyrosine kinase inhibitors wherein the synthesis with preferred R groups is illustrated (boronic acid, Scheme 1; OH, Scheme 2; an aliphatic amide extension, Scheme 3; and a phosphonic acid Scheme 4).

Scheme 1

1

2

3

4
Inhibition of pp60c-src:
62% @ 100 µM

- 55 -

Methyl 5-hydroxy-2-indolecarboxylate (1)

Dissolved 3.50 g 5-hydroxy-2-indolecarboxylic acid in anh. MeOH presaturated with HCl gas. Refluxed for 48 hours. Concentrated *in vacuo* and triturated with AcCN x3

5   to remove residual acid. Filtered through silica plug with EtOAc to remove baseline contamination. Recovered 4.32 g (quant. yield) TLC R_f = .78 (EtOAc) 1H NMR (DMSO-d_6): 3.82 (s, 3H), 6.78 (d, J=8.8 Hz, 1H), 6.88 (s, 1H), 6.93 (s, 1H), 7.23 (d, J=8.8 Hz, 1H), 8.90 (s, 1H) 11.62 (s, 1H) FAB(+) MS m/e 191.9 (M+1)

10   **Methyl 5-[(trifluoromethyl)sulfonyloxy]indole-2-carboxylate (2)**

Added 150 ml anh. DCM to 3.24 g (17 mmol) methyl 5-hydroxy-2-indolecarboxylate (1) and 6.67 g (18.7 mm) n-phenyl trifluoromethane sulfonamide at 0°C. Added 2.6 ml triethylamine dropwise at which point clear yellow solution formed. Stirred at 0°C for 1 hour. Warmed to room temperature and stirred for 2 hours. Concentrated *in*

15   *vacuo* and purified through silica gel column (1/1 EtOAc/hexanes). Recovered 4.69 g (86%). TLC R_f = .63 (1/1 EtOAc/hexanes). HPLC R_f = 20.879 1H NMR (DMSO-d_6): 3.87 (s, 3H), 7.25 (s, 1H), 7.31 (d, J=9.2 Hz, 1H), 7.55 (d, J=9.2 Hz, 1H), 7.80 (s, 1H), 12.34 s, 1H) FAB(+) MS m/e 323.1 (M+1).

20   **Methyl 5-methylindole-2-carboxylate, 4,4,5,5-tetramethyl-1,3,2-dioxaborolanemethyl (3)**

500 mg 1.55 mmol methyl 5-[(trifluoromethyl)sulfonyloxy]indole-2-carboxylate (2), 37.9 mg (.05 mmol) PdCl$_2$ (dppf), 432 mg (1.7 mmol) bispinacolatodiboron, 454.8 mg (4.65 mmol) potassium acetate, and 25.7 mg (.05 mmol) dppf were added to a flask

25   and vacuum dried at 40°C for 2 hours. Added 20 ml anh dioxane and heated to 80°C overnight. Reaction turned black as Pd black precipitated out. Filtered off catalyst and ran silica plug to remove baseline impurities. TLC R_f =.51 (1/4 EtOAc/Hexane) Crude product was taken through to next reaction.

30   **Methyl 5-boronyl indole-2-carboxylate (4)**

391.2 mg (1.3 mmol) methyl 5-methylindole-2-carboxylate, 4,4,5,5-tetramethyl-1,3,2-dioxaborolanemethyl (3) was dissolved in EtOAc. 0.25ml (2.6 mmol) diethanolamine

- 56 -

was added, and the reaction was stirred at room temperature overnight. The white ppt which formed was filtered and sonicated in 1 N HCl. The resulting white ppt was filtered, dissolved in MeOH, and concentrated *in vacuo*. Recovered 36.6 mg (13 %). HPLC R_f = 13.912, 1H NMR (DMSO-d_6): 3.85 (s, 3H), 7.15 s, (1H), 7.36 (d, J=8.4 Hz, 1H), 7.67 (d, J= 8.4 Hz, 1H), 7.87 (s, 1H), 8.14 (s, 1H), 11.91 (s, 1H).

Scheme 2

(5-hydroxyindol-2-yl)-N-[(3-methoxyphenyl)methyl]carboxyamide (5)

Dissolved 2.00g (11.3 mmol) 5-hydroxy-2-indolecarboxylic acid, 1.6 ml (12.4 mmol) 3 methoxybenzylamine, and 5.87 g (11.3 mmol) PyBOP in 10 ml anh. DMF. Cooled to 0°C and added 5.9 ml (33.9 mmol) DIEA. Stirred for 5 min at 0°C and allowed to warm to room temperature for 1 hour. Recovered 2.83g (85% yield) TLC R_f =.34 (1/1 EtOAc / hexanes) 1H NMR (DMSO-d_6): 3.70 (s, 3H), 4.43 (d, J= 4.4Hz, 2H) 6.69 (d, J= 8.8 Hz, 1H), 6.78 (d, J= 7.7 Hz, 1H), 6.83 (s, 1H), 6.86 (s, 1H), 6.94 (s, 1H), 7.20 (m, 3H), 8.92 (t, J=4.4 Hz, 1H), 11.36 (s, 1H) FAB(+) MS m/e 297.3 (M+1)

- 57 -

(5-hydroxyindol-2-yl)-N-[(3-hydroxyphenyl)methyl]carboxyamide (6)

Added 20 ml anh. DCM to 200 mg (0.67 mmol) (5-hydroxyindol-2-yl)-N-[(3-methoxyphenyl)methyl]carboxyamide(5) and cooled to -78°C under argon. Added 4.0 ml (4.0 mmol, 6 eq) BBr$_3$. Held at -78°C for 5 min and warmed to rt. After 90

5   min at rt, quenched with H$_2$O and stirred for 10 min. Diluted rxn mix with EtOAc and washed with NaHCO$_3$ and brine. Dried organic layer over MgSO$_4$ and concentrated *in vacuo*. Ran through silica plug to remove baseline contamination. Recovered X mg. (80% yield.) TLC R$_f$=0.21 (1/1 EtOAc/hexanes). ^{1}H NMR (DMSO-d$_6$): 4.38 (d, J= 4.8 Hz, 2H), 6.59 (d, J=8.8 Hz, 1H), 6.71 (m, 3H) 6.83 (d,

10   J=1.8 Hz, 1H), 6.94 (s, 1H), 7.08 (dd, J= 7.7 Hz, 1H), 7.19 (d, J=8.8 Hz, 1H), 8.84 (t, J=5.9Hz), 11.28, (s, 1H).   FAB(+) MS m/e 283.2 (M+1)

Scheme 3

Inhibition of pp60c-src:
39% at 100 µM

15   **N-(1-carbamoyl-2-methylbutyl)(5-hydroxyindol-2-yl)carboxyamide (7)**

100 mg (0.56 mmol) 5-hydroxy-2-indolecarboxylic acid, 103.4 mg (0.62 mmol, 1.1 eq) L-isoleucinamide, and 291 mg (0.56 mmol, 1 eq) PyBOP were all dissolved in 1 ml anh DMF. The solution was cooled to 0° C and 0.3 ml (1.68 mmol, 3 eq) DIEA was added. The reaction mixture was stirred for 1 min at 0° C and at

20   room temperature for 1 hour. The reaction was then diluted with EtOAc and washed with 1 N HCl x3 and sat'd NaHCO3 x 3. The organic layer was dried over MgSO4, and concentrated *in vacuo* to give 166.7 mg (91 % yield.) TLC R$_f$=0.08 (1/1 EtOAc/hexanes). ^{1}H NMR (DMSO-d$_6$): 0.83 (m, 6H), 1.15 (m, 2H), 1.68 (m, 1H), 1.83 (m, 1H), 4.29 (t, J=8.8 Hz, 1H), 6.69 (d, J=8.5 Hz, 1H), 6.83 (s, 1H), 7.01, (s,

- 58 -

1H), 7.06 (s, 1H), 7.19 (d, J=8.4 Hz, 1H), 7.48, (s, 1H), 8.00 (d, 9.2 Hz, 1H), 8.76 (s,

1H), 11.3, (s, 1H). FAB(+) MS m/e 290.1 (M+1)

Scheme 4

1

2

8

9

Inhibition of pp60c-src:
11% at 500 μM

Methyl 5-dibenzylphosphorylindole-2-carboxylate (8)

200 mg (0.62 mmol) methyl 5-[(trifluoromethyl)sulfonyloxy]indole-2-carboxylate (2), 195.8 mg (.74 mmol,1.2 eq) dibenzylphosphite, 0.14 ml (0.81 mmol, 1.3 eq) DIEA, and 35.7 mg (0.03 mmol, 5 mol %) Pd(PPh$_3$)$_4$ were all dissolved in anh AcCN under argon. The reaction mix was heated to 80°C overnight. The solvent was removed under reduced pressure, and the title compound was isolated by silica gel chromatography. 130 mg (50% yield). TLC R$_f$=0.28 (1/1 EtOAc/hexanes) [1]H NMR

- 59 -

(DMSO-d$_6$): 3.85 (s, 3H), 4.98-5.01 (m, 4H), 7.28-7.32 (m, 11H), 7.53-7.55 (m, 2H), 8.17 (d, J=14.6 Hz, 1H) ^{31}P NMR (DMSO-d$_6$): 23.89.

Methyl 5-phosphonolindole-2-carboxylate

5   Methyl 5-dibenzylphosphorylindole-2-carboxylate **(8)** (125 mg) was dissolved in 10 ml MeOH. 20 mg Pd-C was added and the mixture was hydrogenated in a Parr apparatus overnight. Filtered off catalyst and removed solvent under reduced pressure. Obtained 72.5 mg (73% yield). TLC R$_f$ = baseline in EtOAc. ^{1}H NMR (DMSO-d$_6$): 3.84 (s, 3H), 7.24 (s, 1H), 7.44-7.49 (m, 2H), 8.01 (d, J=14.3 Hz, 1H)

10   12.11 (s, 1H) ^{31}P NMR (DMSO-d$_6$): 17.22.

        The ester compounds in this example could be increased in potency by converting the ester to an amide and/or adding additional specificity elements.

15

Example 4 – Synthesis of Further Indole Derivative Protein Kinase Inhibitors

        The synthesis of some further elaborated indole inhibitors is illustrated in below. These syntheses should result in compounds with greater potency against

20   pp60c-src and other tyrosine kinases. The methyl ester group can be subsequently converted into various amide derivatives to increase potency.

Scheme 1:

5

Scheme 2:

Scheme 3:

5

Example 5 – Toxicity of Src inhibitors

There is considerable recent literature support for targeting pp60^{c-src} (Src) as a broadly useful approach to cancer therapy without resulting in serious toxicity. For example, tumors that display enhanced EGF receptor PTK signaling, or overexpress the related Her-2/neu receptor, have constitutively activated Src and enhanced tumor invasiveness. Inhibition of Src in these cells induces growth arrest, triggers apoptosis, and reverses the transformed phenotype (Karni et al., 1999). It is known that abnormally elevated Src activity allows transformed cells to grow in an anchorage-independent fashion. This is apparently caused by the fact that extracellular matrix signaling elevates Src activity in the FAK/Src pathway, in a coordinated fashion with mitogenic signaling, and thereby blocks an apoptotic mechanism which would normally have been activated. Consequently FAK/Src inhibition in tumor cells may induce apoptosis because the apoptotic mechanism which would have normally become activated upon breaking free from the extracellular matrix would be induced (Hisano et al., 1997). Additionally, reduced VEGF mRNA expression was noted upon Src inhibition and tumors derived from these Src-inhibited cell lines showed reduced angiogenic development (Ellis et al., 1998).

The issue of potential toxicity of Src inhibition has been addressed with very promising results. For example, a knock-out of the Src gene in mice led to only one defect, namely osteoclasts that fail to form ruffled borders and consequently do not resorb bone. However, the osteoclast bone resorb function was rescued in these mice by inserting a kinase defective Src gene (Schwartzberg et al., 1997). This suggested that Src kinase activity can be inhibited *in vivo* without triggering the only known toxicity because the presence of the Src protein is apparently sufficient to recruit and activate other PTKs (which are essential for maintaining osteoclast function) in an osteoclast essential signaling complex.

Src has been proposed to be a "universal" target for cancer therapy since it has been found to be overactivated in a growing number of human tumors, in addition those noted above (Levitzki, 1996). The potential benefits of Src inhibition for cancer therapy appear to be four-fold based upon the cited, and additional, literature. They are: 1) Inhibition of uncontrolled cell growth caused by autocrine growth factor loop effects, etc. 2) Inhibition of metastasis due to triggering apoptosis upon breaking free

from the cell matrix. 3) Inhibition of tumor angiogenesis via reduced VEGF levels.
4) Low toxicity.

The initial non-peptide Src inhibitors have also shown very encouraging
results in four different series of cell culture assays. 1) In the NIH 60-tumor cell
5   panel assay, broad activity (as one would expect for a Src inhibitor) was seen against
the tumor cell lines, including the prostate lines. For example, three of the inhibitors
gave the following growth inhibition IC_{50}'s against the NIH prostate cancer cell lines:
TOM 2-32 (PC-3, 15 μM; DU-145, 38 μM), TOM 2-47 (PC-3, 19 μM), KLM 2-31
(PC-3, 39 μM; DU-145, > 100 μM). 2) In the v-Src transformed normal rat kidney
10   cell line (LA25) TOM 2-47 & TOM 2-32 specifically blocked the v-Src induced cell
growth without inhibiting the normal growth of the parent non-transformed cells.
This result showed that the inhibitors do not affect normal cells but are effective in
blocking Src induced cell transformation. 3) The Src inhibitors to the cancer drugs
etoposide, taxol, doxorubicin and cisplatin in ovarian tumors from three different
15   patients and an abdominal carcinoma from another patient. In all cases, the Src
inhibitors were at least as effective, and typically more effective, than the known
cancer drugs, with full efficacy seen at the lowest dose tested (3 μM). As a
representative example, a comparison of taxol and doxorubicin (they were more
effective than etoposide & cisplatin in this particular tumor cell culture) with the three
20   Src inhibitors mentioned above utilizing ovarian tumor cells from tumor N015 is
shown in Figure 15A. 4) The Src inhibitors were also tested for inhibition of normal
human fibroblast cell growth and found no inhibition of normal cell growth (both
subconfluent and confluent; some enhanced growth was observed instead), indicating
that these inhibitors are not toxic to normal cells even at a 10-fold higher
25   concentration. An example of his data is given in Figure 15B.

Overall, the cell data obtained thus far shows what one might expect for Src
inhibitors, i.e. broad activity against many cancer cell lines with little or no normal
cell toxicity.

The preliminary Src inhibitors are lead structures from which it is possible to
30   design more potent and selective inhibitors. In addition to utilizing the tyrosine
kinase crystal structures, molecular modeling studies can be carried out with the
natural product tyrosine kinase inhibitor damnacanthal (Faltynek et al., 1995) to

investigate its peptide-competitive binding mode. These additional modeling studies are enable one to design further analogs of Src inhibitors wherein the key pharmacophore elements of damnacanthal are incorporated into the new inhibitors. Their syntheses will be undertaken and the isolated Src testing done as reported

5   (Marsilje 2000).

Although preferred embodiments have been depicted and described in detail herein, it will be apparent to those skilled in the relevant art that various modifications, additions, substitutions, and the like can be made without departing from the spirit of the invention and these are therefore considered to be within the

10   scope of the invention as defined in the claims which follow.

- 65 -

LITERATURE CITED

The following references which were cited herein, are hereby incorporated by reference into this application:

5

Ajay, Murcko, M. A. (1995) *Computational Methods to Predict Binding Free Energy in Ligand-Receptor Complexes*. J. Med. Chem., **38**, 4953-4967.

Alberts, B., Bray, D., Lewis, J., Raff, M., Roberts, K. & Watson, J. D. (1994)
10 Molecular Biology Of The Cell, 3rd ed., Garland Publishing, Inc., New York, pp 97, 508 & 667.

Alfaro-Lopez, J., Yuan, W., Phan, B. C., Kamath, J., Lou, Q., Lam, K. S., Hruby, V. J. (1998) *Discovery of a Novel Series of Potent and Selective Substrate-Based*
15 *Inhibitors of p60c-src Protein Tyrosine Kinase: Conformational and Topographical Constraints in Peptide Design*. J. Med. Chem., **41**, 2252-2260.

Backes, B. J., Virgilo, A. A., Ellman, J. A. (1996) *Activation Method to Prepare a Highly Reactive Acylsulfonamide "Safety-Catch" Linker for Solid-Phase Synthesis*. J.
20 Am. Chem. Soc., **118**, 3055-3056.

Baggio, R., Elbaum, D., Kanyo, Z. F., Carroll, P. J., Cavalli, C., Ash, D. E., Christianson, D. W. (1997) *Inhibition of Mn2+-Arginase by Borate Leads to the Design of a Transition State Analog Inhibitor, 2(S)-Amino-6-boronohexanoic Acid*. J.
25 Am. Chem. Soc., **119**, 8107-8108.

Barnekow, A.; Paul, E.; Schartl, M. (1987) *Expression of the c-src protooncogene in human skin tumors*. Cancer Res., **47**, 235-240.

30 Benson, W. H., Birge, W. J., Dorough, H. W. (1984) Environ. Toxicol. Chem., **3**, 209. Chem. Abstr. **101**:124626g.

- 66 -

Bhagwat, S. S., Gude, C. (1994) *N-Alkylation of indole ring using Mitsunobu reaction.* Tet. Lett., **35**, 1847-1850.

Bjorge, J. D., O'Connor, T. J., Fujita, D. J. (1996) *Activation of human pp60^{c-src}.* B iochemistry & Cell Biology, **74**, 477-484.

Bjelfman, C.; Hedborg, F.; Johansson, I.; Nordenskjold, M.; Pahlman, S. (1990) *Expression of the neuronal for of pp60c-src in neuroblastoma in relation to clinical stage and prognosis.* Cancer Res, **50**, 6908-6914.

Bohacek, R. S., McMartin, C., Guida, W. C. (1996) *The Art and Practice of Structure-Based Drug Design: A Molecular Modeling Perspective.* Medicinal Research Reviews, **16**, 3-50 (see p. 43).

Boyd, M. R., Paull, K. D. (1995) *Some practical considerations and applications fo the National Cancer Institute in vitro anticancer drug discovery screen.* Drug Development Research, **34**, 91-109.

Brooks, S. P. J. & Storey, K. B. (1992) *Bound and Determined: A Computer Program for Making Buffers of Defined Ion Concentrations.* Analytical Biochemistry, **201**, 119-126.

Brown, D. (1997) *Future Pathways for Combinatorial Chemistry.* Molecular Diversity, **2(4)**, 217-222.

Budde, R. J. A., McMurray, J. S., Saya, H., Gallick, G. E. & Levin, V. A. (1995) *Discovery, Development, and Testing of Substrates and Inhibitors of pp60^{c-src}.* International Journal of Pharmacognosy, **33**, 27-34.

Budde, R. J. A., Ke, S., Levin, V. A. (1994) *Activity of pp60c-src in 60 different cell lines derived from human tumors.* Cancer Biochem. Biophys., **14**, 171-175.

- 67 -

Burger, A. M., Kaur, G., Alley, M. C., Supko, J. G., Malspeis, L., Grever, M. R. & Sausville, E. A. (1995) *Tyrphostin AG17, [(3,5-Di-tert-butyl-4-hydroxybenzylidene)-malonitrile], inhibits cell growth by disrupting mitochondria.* Cancer Research, **55**, 2794-2799.

Burke, T. R.; Lim, B.; Marquez, V. E.; Li, Z-H.; Bolen, J. B.; Stefanova, I.; Horak, I. D. (1993) J. Med. Chem. **36**, 425.

Choi, S. (1999), Ph.D. Thesis SUNY at Buffalo, Buffalo, NY.

Cooper, C. M. (1990) Oncogenes. Jones and Bartlett Publishers, Boston, MA.

Coughlin, J. R. (1996) *Inorganic borates-chemistry, human exposure, and health and regulatory guidelines.* J. Trace Elements in Experimental Medicine, **9**, 137-151.

Courtneidge, S. A. (1994) *Protein tyrosine kinases, with emphasis on the Src family.* Seminars in Cancer Biology, **5**, 239-246.

Cox, S., Radzio-Andzelm, E. & Taylor, S. S. (1994) *Domain movements in protein kinases.* Current Opinion in Structural Biology, **4(6)**, 893-901.

Culver, B. D., Hubbard, S. A. (1996) *Inorganic boron health effects in humans- and aid to risk assessment and clinical judgment.* J. Trace Elements in Experimental Medicine, **9**, 175-184.

Davis, P. D.; Hill, C. H.; Keech, E.; Lawton, G.; Nixon, J. S.; Sedgwick, A. D.; Wadsworth, J.; Westmacott, D.; Wilkinson, S. E. (1989) FEBS Lett. **259(1)**, 61.

Davis, P. D.; Elliott, L. H.; Harris, W.; Hill, C. H.; Hurst, S. A.; Keech, E.; Kumar, M. K. H.; Lawton, G.; Nixon, J. S.; Wilkinson, S. E. (1992) J. Med. Chem. **35**, 994.

5

10

15

20

25

30

Ellis, L.M., Staley, C.A., Liu, W., Fleming, R.Y., Parikh, N.U., Bucana, C.D., & Gallick, G.E. (1998) *Down-regulation of vascular endothelial growth factor in a human colon carcinoma cell line transfected with an antisense expression vector specific for c-src.* Journal of Biological Chemistry **273** (2):1052-1057.

Ezquerra, J., Pedregal, C., Lamas, C., Barluenga, J., Perez, M., Garcia-Martin, M. A., Gonzalez, J. M. (1996) *Efficient reagents for the synthesis of 5-, 7-, and 5,7-substituted indoles starting from aromatic amines: scope and limitations.* J. Org. Chem., **61**, 5804-5812.

Faltynek, C., et al. (1995) *Damnacanthal is a highly potent, selective inhibitor of p56lck tyrosine kinase activity.* Biochemistry **34**, 12404-12410.

Faltynek, C. R.; Wang, S.; Miller, D.; Mauvais, P.; Gauvin, B.; Reid, J.; Xie, W.; Hoekstra, S.; Juniewicz, P.; Sarup, J.; Lehr, R.; Sawutz, D. G.; Murphy, D. J. (1995) Enzyme Inhibition **9**, 111.

Fanning, P.; Bulovas, K.; Saini, K.S.; Libertino, J.A.; Joyce, A.D.; Summerhayes, I.C. (1992) *Elevated expression of pp60^{c-src} in low grade human bladder carcinoma.* Cancer Research, **52**, 1457-1462.

Fredenhagen, A.; Mett, H.; Meyer, T.; Buchdunger, E.; Regenass, U.; Roggo, B. E.; Petersen, F. J. (1995) Antibiotics **48**, 1355.

Froyen, P. (1997) Tetrahedron Lett. **38**(30), 5359.

Fry, D. W., Kraker, A. J., McMichael, A., Ambroso, L. A., Nelson, J. M. Leopold, W. R., Connors, R. W. & Bridges, A. J. (1994) *A Specific Inhibitor of the Epidermal Growth Factor Receptor Tyrosine Kinase.* Science, **265**, 1093-1095.

Glass, D. B., Cheng, H.-C., Mende-Mueller, L., Reed. J. & Walsh, D. A. (1989) *Primary structure determinants essential for potent inhibition of cAMP-dependent*

- 69 -

protein kinase by inhibitory peptides corresponding to the active portion of the heat-stable inhibitor protein. J. Biol. Chem., **264**, 8802-8810.

Groundwater, P. W., Solomons, K. R. H., Drewe, J. A. & Munawar, M. A. (1996)
5   *Protein Tyrosine Kinase Inhibitors.* Progress in Medicinal Chemistry, **33**, 233-329.

Hanks, S. K. & Hunter, T. (1995) Protein kinases. 6. *The eukaryotic protein kinase superfamily: Kinase (catalytic) domain structure and classification.* FASEB J., **9**, 576-596.

10

Hanke, J. H., Gardner, J. P., Dow, R. L., Changelian, P. S., Brissette, W. H., Weringer, E. J., Pollok, B. A. & Connelly, P. A. (1996) *Discovery of a novel, potent, and Src family-selective tyrosine kinase inhibitor.* J. Biol. Chem., **271**, 695-701.

15   **Hisano**, C., Nakano, S., Fujishima, H., Masumoto, N., Tatsumoto, T., & Niho. Y. (1997) *src oncogene inhibits detachment-induced apoptosis through constitutive activation of p125FAK in HAG-1 human epithelial cells.* Proc. Annu. Meet. Am. Assoc. Cancer Res. **38**:A1925.

20   **Hsiao**, G. K., Hangauer, D. G. (1998) *A Facile Synthesis of tert-Butyl 2-[(Benzyloxycarbonyl)amino]-3-(4,4,5,5-tetramethyl-1,3,2-dioxaborolan-2-yl)propionate: An Orthogonally Protected Boronic Acid Analog of Aspartic Acid.* Synthesis, 1043-1046.

25   **Hsu**, C-Y., J., Jacoski, M. V., Maguire, M. P., Spada, A. P. & Zilberstein, A. (1992) *Inhibition Kinetics and Selectivity of the Tyrosine Kinase Inhibitor Erbstatin and a Pyridone-based Analog.* Biochemical Pharmacology, **43**, 241-2477.

Huang, C-K., Wu, F-Y., Ai, Y-X. (1995) *Polyhydroxylated 3-(N-phenyl) carbamoyl-*
30   *2-iminochromene derivatives as potent inhibitors of tyrosine kinase p60c-src.* Bioorg. & Med. Chem. Lett., **5**, 2423-2428.

- 70 -

Hubbard, S. R., Wei, L, Ellis, L, & Hendrickson, W. A. (1994) *Crystal structure of the tyrosine kinase domain of the human insulin receptor,* Nature, **372**, 746-754.

Hubbard, S. R. (1997) *Crystal structure of the activated insulin receptor tyrosine kinase in complex with peptide substrate and ATP analog.* The EMBO Journal, **16**, 5572-5581.

Hughes, R. L., Smith, I. C., Lawless, E. W. (1967) Production of the Boranes and Related Rearch, Holtzman R.T., Ed., Academic Press, New York, pp 291-294.

Hunter, T. (1987) *A thousand and one protein kinases.* Cell, **50**, 823-829.

Hunter, T. (1994) *1001 protein kinases redux-towards 2000.* Seminars in Cell Biology, **5**, 367-376.

Hunter, T. (1998) *The Croonian Lecture 1997. The phosphorylation of proteins on tyrosine: its role in cell growth and disease.* Philosophical Transactions of the Royal Society of London - Series B: Biological Sciences 353 (1368):583-605.

Hutchins, C., Greer, J. (1991) *Comparative modeling of proteins in the design of novel renin inhibitors.* Critical Reviews in Biochemistry & Molecular Biology, **26**, 77-127.

Ishiyama, T., Murata, M., Miyaura, N. (1995) *Palladium(0)-catalyzed cross-coupling reaction of alkoxydboron with haloarenes: A direct procedure for arylboronic esters.* J. Org. Chem., **60**, 7508-7510.

Ishiyama, T., Itoh, Y., Kitano, T., Miyaura, N. (1997) *Synthesis of arylboronates via the palladium(0)-catalyzed cross-coupling reaction of tetra(alkoxo)diborons with aryl triflates.* Tet. Lett., **38**, 3447-3450.

Karni, R., Jove R., & Levitzki A. (1999) *Inhibition of pp60c-src reduces Bcl-X expression and reverses the transformed phenotype of cells overexpressing EGF and HER-2 receptors.* Oncogene 18(33): 4654-4662.

5   Kelloff, G. J., Fay, J. R., Steele, V. E., Lubet, R. A., Boone, C. W., Crowell, J. A. (1996) *Epidermal growth factor receptor tyrosine kinase inhibitors as potential cancer chemopreventatives.* Cancer Epidemiology, Biomarkers & Prevention, 5, 657-666.

10   Kettner, C. A., Shenvi, A. B. (1984) *Inhibition of the Serine Proteases Leukocyte Elastase, Pancreatic Elastase, Cathepsin G, and Chymotrypsin by Peptide Boronic Acids.* J. Biol. Chem., 259, 15106-15114.

Kim. M. H., Lai, J. H. & Hangauer, D. G. (1994) *Tetrapeptide tyrosine kinase*
15   *inhibitors: Enantioselective synthesis of p-hydroxymethyl-L-phenylalanine, incorporation into a tetrapeptide, and subsequent elaboration into p-(R,S-hydroxyphosphonomethyl)-L-phenylalanine.* Int. J. Peptide Protein Res., 44, 457-465.

Kinder, D. H., Frank, S. K., Ames, M. M. (1990*) Analogues of Carbamyl Aspartate*
20   *as Inhibitors of Dihydroorotase: Preparation of Boronic Acid Transition-State Analogues and a Zinc Chelator Carbamylhomocysteine.* J. Med. Chem., 33, 819-823.

Klein, G. (1990) *Multistep emancipation of tumors from growth control: can it be curbed in a single step?* BioEssays, 12, 347-350.
25

Knighton, D. R., Cadena, D. L., Zheng, J., Ten Eyck, L. F., Taylor, S. S. & Sowadski, J. M. (1993) *Structural features that specify tyrosine activity deduced from homology modeling of the epidermal growth factor receptor.* Proc. Natl. Acad. Sci. U.S.A., 90(11), 5001-5.
30

Kolibaba, K. S. & Druker, B. J. (1997) *Protein tyrosine kinases and cancer.* Biochimica et Biophysica Acta, 1333: F217-F248.

- 72 -

Lai, J. H., Marsilje, T. M., Choi, S., Nair, S. A., Hangauer, D. G. (1998) *The design, synthesis and activity of pentapeptide pp60c-src inhibitors containing L-phosphotyrosine mimics*. J. Peptide Res., **51**, 271-281.

5   Lai, J. H., Pham, H. & Hangauer, D. G. (1996) *Synthesis of a Vicinal Tricarbonyl Amide Derivative of L-Phenylalanine*. J. Org. Chem., **61**, 1872-1874.

Lam, K. S. (1997) *Application of Combinatorial Library Methods in Cancer Research an Drug Discovery*. Anti-Cancer Drug Design, **12(3)**, 145-167.

10

Lawrence, D.S. & Niu, J. (1998) *Protein Kinase Inhibitors: The Tyrosine-Specific Protein Kinases*. Pharmacol. Ther., **77(2)**, 81-114.

Levitzki, A. (1996a) *Targeting signal transduction for disease therapy*. Current
15   Opinion in Cell Biology, **8**, 239-244.

Levitzki, A. (1996b) *SRC as a target for anti-cancer drugs*. Anti-Cancer Drug Design, **11**, 175-182.

20   Levitzki, A.; Gazit, A. (1995) *Tyrosine Kinase Inhibition: An Approach to Drug Development*. Science, **267**, 1782-1788.

Li, H., Liu, T.F., Lazrak, A., Peracchia, C., Goldberg, G. S., Lampe, P. D., Johnson, R. G. (1996) *Properties and regulation of gap junctional hemichannels in the plasma*
25   *membranes of cultured cells*. J. Cell. Biol., **134**, 1019-1030.

Loomis, W. D. & Durst, R. W. (1992) *Chemistry and biology of boron*. BioFactors, **3**, 229-239.

30   Lou, Q., Leftwich, M. E., McKay, T., Salmon, S. E., Rychetsky, L. & Lam, K. S. (1997) *Potent Pseudosubstrate-based Peptide Inhibitors for p60^{c-src} Protein Tyrosine Kinase*. Cancer Research, **57(10)**, 1877-1881.

- 73 -

Lou, Q., Leftwich, M. E. & Lam, K. S. (1996) *Identification of GIYWHHY as a Novel Peptide Substrate for Human p60c-src Protein Tyrosine Kinase.* Biorganic & Medicinal Chemistry, **4**, 677-682.

5   **Luttrell**, D.K.; Lee, A.; Lansing, T.J.; Crosby, R.M.; Jung, K.D.; Willard, D.; Luther, M.; Rodriguez, M.; Berman, J.; Gilmer, T.M. (1994) *Involvement of pp60^{c-src} with two major signaling pathways in human breast cancer.* Proc. Natl. Acad. Sci. USA, **91**, 83-87.

10   **Lynch**, S.A.; Brugge, J.S.; Fromowitz, F.; Glantz, L.; Wang, P.; Caruso, R.; Viola, M.V. (1993) *Increased expression of the src proto-oncogene in hairy cell leukemia and a subgroup of B-cell lymphomas.* Leukemia, **7**, 1416-1422.

Madhusudan, Trafny, E. A., , Xuong, N-H, Adams, J. A., Ten Eyck, L. F., Taylor, S.
15   S. & Sowadski, J. M. (1994) *cAMP-dependent protein kinase: Crystallographic insights into substrate recognition and phosphotransfer.* Protein Science, **3**, 176-187.

Mao, W. G., Irby, R., Coppola, D., Fu, L., Turner, J. (1997) *Activation of c-src by receptor tyrosine kinases in human colon cancer cells with high metastatic potential.*
20   Oncogene, **15**, 3083-3090.

Marsilje, T.H., Milkiewicz, K.L., & Hangauer, D.L. (2000) *The design, synthesis and activity of non-ATP competitive inhibitors of pp60c-src tyrosine kinase 1. Hydroxynaphthalene Derivatives.* Bioorganic and Medicinal Chemistry Letters, in
25   press.

Marx, J. (1990) *Oncogenes evoke new cancer therapies.* Science, **249**, 1376-1378.

National Cancer Institute (1989) Survey of Compounds which have been tested for
30   carcinogenic activity. NIH Publication No. 49-468, p. 16.

- 74 -

Matteson, D. S., Kandil, S. A., Soundararajan, R. (1990) *Synthesis of Asymmetrically Deuterated Glycerol and Dibenzylglyceraldehyde via Boronic Esters.* J. Am. Chem. Soc., **112**, 3964-3969.

5   Matteson, D. S. (1988) Acc. Chem. Res., **21**, 294-300.

Matteson, D. S., Kandil, A. A. (1987) *Conversion of α-halo boronic esters to inverted α-(methylsulfonyl)oxy boronic esters.* J. Org. Chem., **52**, 5121-5124.

10   Matteson, D. S., Soloway, A. H., Tomlinson, D. W., Campbell, J. D., Nixon, G. A. (1964) J. Med. Chem., **7**, 640.

Mazurenko, N.N.; Kogen, E.A.; Zborovskaya, I.B.; Kisseljov, F.L. (1992) *Expression of pp60^{c-src} in human small cell and non-small cell lung carcinomas.*
15   European J. of Cancer, **28**, 372-377.

Milkiewicz, K.; Marsilje, T.; Woodward Jr, R.; Bifulco Jr, N.; Hangauer, M.; Hangauer, D.G. (2000) *The design, synthesis and activity of non-ATP competitive inhibitors of pp60c-src tyrosine kinase 2. Hydroxyindole Derivatives.* Bioorganic and
20   Medicinal Chemistry Letters, in press.

Mohammadi, M., Schlessinger, J., Hubbard, S. R. (1996) *Structure of the FGF Receptor Tyrosine Kinase Domain Reveals a Novel Autoinhibitory Mechanism.* Cell, **86**, 577-587.
25
Mohammadi, M., McMahon, G., Li, S., Tang, C., Hirth, P., Yeh, B. K., Hubbard, S. R., Schlessinger, J. (1997) *Structures of the Tyrosine Kinase Domain of Fibroblast Growth Factor Receptor in Complex with Inhibitors.* Science, **276**, 955-960.

30   Morin, C. (1994) *The Chemistry of Boron Analogues of Biomolecules.* Tetrahedron, **50**, 12521-12569.

- 75 -

Murakami, Y., Otsuka, K. Wada, Y., Morikawa, A. (1990) *The partial oxidation of ethane over a B_2O_3-Al_2O_3 catalyst.* Bull. Chem. Soc. Jpn., **63**, 340-346.

Nair, S. A., Kim, M. K., Warren, S. D.,Choi, S., Songyang, Z., Cantley, L. C. &
5   Hangauer, D. G.(1995). *Identification of Efficient Pentapeptide Substrates for the Tyrosine Kinase pp60^{c-src}.* J. Med. Chem., **38**, 4276-4283.

Nair, S. A., Lee, B. & Hangauer, D. G. (1995b). *Synthesis of Orthogonally Protected L-Homocysteine and L-2-Amino-4-phosphonobutanoic Acid From L-Homoserine.*
10   Synthesis, **7**, 810-814.

Nielsen, F. H. (1997) *Boron in human and animal nutrition.* Plant & Soil, **193**, 199-208.

15   Otsuka, K., Uragami, Y., Hatano, M. (1992) *The partial oxidation of ethane to acetaldehyde.* Catalysis Today, **13**, 667-672.

Parsons, J. T. & Parsons, S. J. (1997) *Src family protein tyrosine kinases: cooperating with growth factor and adhesion signaling pathways.* Current Opinion in
20   Cell Biology, **9**, 187-192.

Patrick, D. R. & Heimbrook, D. C. (1996) *Protein Kinase Inhibitors For The Treatment of Cancer.* Drug Discovery Today, **1**, 325-330.

25   Pavia, M. R., Cohen, M. P., Dilley, G. J., Dubuc, G. R., Durgin, T. L., Forman, F. W., Hediger, M. E., Milot, G., Powers, T. S., Sucholeiki, I., Zhou, S. & Hangauer, D. G. (1996) *The Design and Synthesis of Substituted Biphenyl Libraries.* Biorganic & Medicinal Chemistry, **4**, 659-666.

30   Posner, I., Engel, M., Gazit, A. & Levitzki, A. (1994) *Kinetics of Inhibition by Tyrphostins of the Tyrosine Kinase Activity of the Epidermal·Growth Factor Receptor and Analysis by a New Computer Program.* Molecular Pharmacology, **45**, 673-683.

- 76 -

Powis, G. (1991) *Signal targets for anticancer drug development.* TIPS, 188-194.

Ramdas, L., Obeyesekere, N. U., McMurray, J. S., Gallick, G. E., Seifert, W. E. Jr. &
Budde, R. J. (1995) *A tyrphostin-derived inhibitor of protein tyrosine kinases:*
5   *isolation and characterization.* Archives of Biochemistry & Biophysics, **323**, 237-
242.

Ramdas, L., McMurray, J. S. & Budde, R. J. (1994) *The degree of inhibition of*
protein tyrosine kinase activity by tyrphostin 23 and 25 is related to their instability.
10   Cancer Research, **54**, 867-869.

Rewcastle, G. W., Palmer, B. D., Thompson, A. M., Bridges, A. J., Cody, D. R.,
Zhou, H. Fry, D. W., McMichael, A. & Denny, W. A. (1996) *Tyrosine Kinase*
Inhibitors. 10. Isomeric 4-[(3-Bromophenyl)amino]pyrido[d]-pyrimidines Are Potent
15   *ATP Binding Site Inhibitors of the Tyrosine Kinase Function of the Epidermal Growth*
Factor Receptor. J. Med. Chem., **39**, 1823-1835.

Rudd, C. E.; Janssen, O.; Prasad, K.V.S.; Raab, M.; da Silva, A.; Telfer, J.C.;
Yamamoto, M. (1993) *src-related protein tyrosine kinases and their surface*
20   *receptors.* Biochimica et Biophysica Acta, **1155**, 239-266.

Saperstein, R., Vicario, P. P., Strout, H. V., Brady, E., Slater, E. E., Greenlee, W. J.,
Ondeyka, D. L., Patchett, A. A. & Hangauer, D. G. (1989) *Design of a selective*
insulin receptor tyrosine kinase inhibitor and its effect on glucose uptake and
25   *metabolism in intact cells.* Biochemistry, **28**, 5694-5701.

Sawutz, D. G.; Bode, D. C.; Briggs, G. M.; Reid, J. R.; Canniff, P.; Caldwell, L.;
Faltynek, C. R.; Miller, D.; Dunn, J. A.; Garavilla, L.; Guiles, J. W.; Weigelt, C.;
Michne, W.; Treasurywala, A. M.; Silver, P. J. (1996) Biochem. Pharmacol. **51**, 1631.
30

Schwartzberg, P. L., et al. (1997) *Rescue of osteoclast function by transgenic*
expression of kinase-deficient Src in src-/- mutant mice. Genes & Development **11**:
2835-2844.

- 77 -

Shiraishi, T., Owada, M. K., Tatsuka, M., Yamashita, T., Watanabe, K., Kakunaga, T. (1989) *Specific Inhibitors of Tyrosine-specific Protein Kinases: Properties of 4-hydroxycinnamamide derivatives in vitro.* Cancer Research, **49**, 2374-2378.

5

Showalter, H. H. & Kraker, A. J. (1997) *Small molecule inhibitors of the platelet-derived growth factor receptor, the fibroblast growth factor receptor, and src family tyrosine kinases.* Pharmacology & Therapeutics, **76**, 55-71.

10   Sicheri, F., Moarefi, I. & Kuriyan, J. (1997) *Crystal structure of the Src family tyrosine kinase Hck.* Nature, **385**, 602-609.

Skordalakes, E., Tyrell, R., Elgendy, S., Goodwin, C. A., Green, D., Dodson, G., Scully, M. F., Freyssinet, J-M. H., Kakkar, V. V., Deadman, J. J. (1997)

15   *Crystallographic Structures of Human α-Thrombin Complexed to Peptide Boronic Acids Lacking a Positive Charge at P_1. Evidence of Novel Interactions.* J. Am. Chem. Soc., **119**, 9935-9936.

Snyder, H. R., Kuck, J. A., Johnson, J. R. (1938) J. Am. Chem. Soc., **60**, 105.

20

Soloway, A. H., Whitman, B., Messer, J. R. (1962) J. Med. Pharm. Chem., **7**, 640.

Soloway, A. H., Whitman, B., Messer, J. R. (1960) J. Pharmacology and Experimental Therapeutics, **129**, 310-314.

25

Soloway, A. H. (1958) Science, **128**, 1572.

Songyang, Z, Blechner, S., Hoagland, N., Hoekstra, M. F., Piwnica-Worms, H. & Cantley, L. C. (1994) *Use of an oriented peptide library to determine the optimal*

30   *substrates of protein kinases.* Current Biology, **4**, 973-982.

Songyang, Z., Carraway III, K. L., Eck, M. J., Harrison, S. C., Feldman, R. A., Mohammadl, M., Schlessinger, J., Hubbard, S. R., Smith, D. P., Eng. C., Lorenzo, J.

- 78 -

J., Ponder, B. A. J., Mayer, B. J. & Cantley, L. C. (1995) *Protein tyrosine kinases and SH2 domains have overlapping specificities.* Nature, 373, 536-539.

Staley, C. A.; Parikh, N. U.; Gallick, G. E. (1997) Cell Growth & Differentiation 8(3), 269.

Stanwell, C., Burke, T. R. & Yuspa, S. H. (1995) *Erbstatin Analogue Methyl 2,5-dihydrocinnamate Cross-links Proteins and is Cytotoxic to Normal and Neoplastic Epithelial Cells by a Mechanism Independent of Tyrosine Kinase Inhibition.* Cancer Research, 55, 4950-4956.

Stanwell, C., Ye, B. & Burke, T. R. (1996) *Cell Protein Cross-linking by Erbstatin and Related Compounds.* Biochemical Pharmacology, 52, 475-480.

Takeshima, E.; Hamaguchi, M.; Watanbe, T.; Akiyama, S.; Kataoka, M.; Ohnishi, Y.; Xiao, H.; Hagai, Y., Taka, H. (1991) *Aberrant elevation of tyrosine-specific phosphorylation in human gastric cancer cells.* Japan J. Cancer Res., 82, 1428-1435.

Talamonti, M.S.; Roh, M.S.; Curley, S.A.; Gallick, G.E. (1993) *Increase in activity and level of pp60^{c-src} in progressive stages of human colorectal cancer.* J. of Clinical Investigation, 91, 53-60.

Taniyama, K., Fujiwara, H., Kuno, T., Saito, N., Shuntoh, H., Sakaue, M. (1989) *Acute and subacute toxicity of 10B-paraboronophenylalanine.* Pigment Cell Research, 2, 291-296.

Taylor, S. J., Shalloway, D. (1996) *Src and the control of cell division.* Bioessays, 18, 9-11.

Taylor, S. S., Knighton, D. R., Zheng, J., Sowadski, J. M., Gibbs, C. S. & Zoller, M. J. (1993) *A template for the protein kinase family.* Trends in Biochemical Sciences, 18(3), 84-9.

- 79 -

Taylor, S.S., Radzio-Andzelm, E. (1994) *Three protein kinase structures define a common motif. Stucture*, **2**, 345-355.

5   Thakkar, K., Geahlen, R. L., Cushman, M. (1993) *Synthesis and protein-tyrosine kinase inhibitory activity of polyhydroxylated stilbene analogs of piceatannol.* J. Med. Chem., **36**, 2950-2955.

Weinberg, R. A. (1989) *Oncogenes, antioncogenes, and the molecular basis of*
10   *multistep carcinogenesis.* Cancer Research, **49**, 3713-3721.

Wolfe, J. P., Ahman, J., Sadighi, J. P., Singer, R. A., Buchwald, S. L. (1997) *An ammonia equivalent for the palladium-catalyzed amination of aryl halides and triflates.* Tet. Lett., **38**, 6367-6370.

15

Wong, T.W. & Goldberg, A. R. (1984) *Kinetics and mechanism of angiotensin phosphorylation by the transforming gene product of Rous Sarcoma Virus.* J. Biol. Chem., **259**, 3127-3131.

20   Xu, W., Harrison, S. C. & Eck, M. J. (1997) *Three-dimensional structure of the tyrosine kinase c-Src.* Nature, **385**, 595-602.

Yamaguchi, H. & Hendrickson, W.A. (1996) *Structural basis for activation of human lymphocyte kinase Lck upon tyrosine phosphorylation.* Nature, **384**, 484-489.

25

Yamamoto, T. (1993) *Molecular Basis of Cancer: Oncogenes and Tumor Suppresor Genes.* Microbiol. Immunol. **37**, 11-22.

Zheng, J., Knighton, D. R., Ten Eyck, L. R., Karlsson, R., Xuong, N-H., Taylor, S. S.
30   & Sowadski, J. M. (1993) *Crystal structure of the catalytic subunit of cAMP-dependent protein kinase complexed with MgATP and peptide inhibitor.* Biochemistry, **32**, 2154-61.

Zhanpeisov, N.U., Otsuka, K. (1992) *Cluster quantum chemical study of the mechanism of selective oxidation of ethane to acetaldehyde on boron-phosphorous mixed oxide catalysts.* React. Kinet. Catal. Lett., **48**, 301-308.

What is claimed:

1.   A method for identifying inhibitors of protein kinases comprising:

providing a first module having a one or more functional groups for binding to
catalytic residues of the protein kinase;

combining the first module with a second module which provides a non-
peptide scaffold; and

selecting combinations of the first and second modules which inhibit protein
kinase activity.

2.   The method according to claim 1, wherein said providing a first
module comprises:

attaching the first module to a peptide scaffold;

identifying one or more functional groups which preferentially bind to
catalytic residues of the protein kinase; and wherein said combining the first module
with the second module comprises:

substituting the second module for the peptide scaffold.

3.   The method according to claim 1, wherein the first module comprises a
functional group selected from the group consisting of boronic acid, a hydroxyl group,
phosphonic acid, sulfamic acid, a guanidino group, carboxylic acid, an aldehyde, an
amide, and hydroxymethylphosphonic acid.

4.   The method according to claim 3, wherein the first module comprises
two or more functional groups.

5.   The method according to claim 3, wherein the first module comprises a
boronic acid group.

6.   The method according to claim 3, wherein the first module comprises a
hydroxyl group.

- 82 -

7.   The method according to claim 3, wherein the first module comprises a amide group.

8.   The method according to claim 7, wherein the amide group is a vicinal

5   tricarbonyl amide.

9.   The method according to claim 1, wherein the second module comprises a group selected from the group consisting of indole, naphthalene, biphenyl, isoquinoline, benzofuran, and benzothiophene.

10

10.   The method according to claim 9, wherein the second module comprises an indole.

11.   The method according to claim 9, wherein the second module

15   comprises naphthalene.

12.   The method according to claim 1, wherein more than one first module is bound to the second module.

20   13.   The method according to claim 1, wherein the first module further comprises a linear chain comprising between one and three carbon atoms which links the first module to the second module.

14.   The method according to claim 13, wherein one of the carbon atoms in

25   the linear chain is substituted with a nitrogen, oxygen or sulfur atom.

15.   The method according to claim 1, wherein the protein kinase is a protein tyrosine kinase.

30   16.   The method according to claim 15, wherein the protein tyrosine kinase is selected from the group consisting of $pp60^{c\text{-}src}$, $p56^{lck}$, ZAP kinase, platelet derived growth factor receptor tyrosine kinase, Bcr-Abl, VEGF receptor tyrosine kinase, and

- 83 -

epidermal growth factor receptor tyrosine kinase, and epidermal growth factor receptor-like tyrosine kinases.

17.   The method according to claim 16, wherein the protein tyrosine kinase is pp60^{c-src}.

18.   The method according to claim 1, wherein the protein kinase is a protein serine kinase.

19.   The method according to claim 15, wherein the protein serine kinase is selected from the group consisting of MAP kinase, protein kinase C, and CDK kinase.

20.   The method according to claim 1, further comprising:
adding one or more specificity side chain elements to the combination of the first and second modules.

21.   A method for identifying improved protein kinase inhibitors, comprising:
providing a first inhibitor produced according to the method of claim 1,
modifying the first module, specificity side chains, or a combination thereof of the first inhibitor; and
identifying modified inhibitors which have an increased ability to inhibit protein kinase activity when compared to the unmodified first inhibitor.

22.   The method according to claim 1, wherein the protein kinase inhibitor inhibits protein kinase activity but does not inhibit ATP binding to the protein kinase.

23.   A method for testing compounds for an ability to inhibit protein kinase activity comprising:
providing a protein kinase inhibitor according to the method of claim 1,
measuring the activity of the protein kinase in the presence of the inhibitor at the same temperature, pH, ionic strength, osmolarity, and free magnesium concentration as found in a cell which expresses the protein kinase; and

- 84 -

comparing the level of protein kinase activity to the level of activity from the protein kinase without the presence of the inhibitor.

24.   A method of inhibiting a protein kinase comprising:

contacting the protein kinase with a compound comprising a first module having a functionality for binding to catalytic residues of the protein kinase and a second module which provides a non-peptide scaffold, wherein the combination of the first and second modules inhibits the protein kinase's activity.

25.   The method according to claim 24, wherein the first module comprises a functional group selected from the group consisting of boronic acid, hydroxy, phosphonic acid, sulfamic acid, a guanidino group, carboxylic acid, an aldehyde, an amide, and hydroxymethylphosphonic acid.

26.   The method according to claim 25, wherein the first module comprises a boronic acid group.

27.   The method according to claim 25, wherein the first module comprises a hydroxyl group

28.   The method according to claim 24, wherein the second module comprises a group selected from the group consisting of indole, naphthalene, biphenyl, isoquinoline, benzofuran, and benzothiophene.

29.   The method according to claim 28, wherein the second module comprises an indole.

30.   The method according to claim 28, wherein the second module comprises naphthalene.

31.   The method according to claim 24, wherein more than one first module is bound to the second module.

32.   The method according to claim 24, wherein a linear chain comprising between one and three carbon atoms links the first module to the second module.

33.   The method according to claim 32, wherein one of the carbon atoms in the linear chain is substituted with a nitrogen, oxygen or sulfur atom.

34.   The method according to claim 24, wherein the protein kinase is a protein tyrosine kinase.

35.   The method according to claim 34, wherein the protein tyrosine kinase is selected from the group consisting of $pp60^{c\text{-}src}$, $p56^{lck}$, ZAP kinase, platelet derived growth factor receptor tyrosine kinase, Bcr-Abl, VEGF receptor tyrosine kinase, and epidermal growth factor receptor tyrosine kinase and epidermal growth factor receptor-like tyrosine kinases.

36.   The method according to claim 34, wherein the protein tyrosine kinase is $pp60^{c\text{-}src}$.

37.   The method according to claim 34, wherein the compound has the following formula:

wherein R1 is H or OH, R2 is H or OH, R3 is OH or H, and R4 is CH_3, $CH_2(CH_3)R$, or $CH_2(CH_3)S$, R5 is OCH_3, H, or OH, R6 is OCH_3, F, H, or OH, and R7 is OCH_3, H, OH, CO_2H, CO_2CH_3, CH_2CO_2H, or $CH_2CO_2CH_3$.

38.   The method according to claim 34, wherein the compound has the following formula:

- 86 -

wherein R1 is OH or H, R2 is OH or H, R3 is OH or H, R4 is OH or H, R5 is OH, OMe, or H, R6 is OH, OMe, or H, R7 is OH, OMe, or H, and X is 0 or 1.

39.   The method according to claim 34, wherein the compound has a specificity group which is an aliphatic amide.

40.   The method according to claim 39, wherein the compound has the following structure:

41.   The method according to claim 24, wherein the protein kinase is a protein serine kinase.

42.   The method according to claim 41, wherein the protein serine kinase is selected from the group consisting of MAP kinase, protein kinase C, and CDK kinase.

43.   The method according to claim 24, wherein the compound further comprises one or more specificity side chain elements attached to the combination of the first and second modules.

44.   A non-peptide protein tyrosine kinase inhibitor having the formula:

wherein R1 is H or OH, R2 is H or OH, R3 is OH or H, and R4 is CH$_3$, CH$_2$(CH$_3$)R, or CH$_2$(CH$_3$)S, R5 is OCH$_3$, H, or OH, R6 is OCH$_3$, F, H, or OH, and R7 is OCH$_3$, H, OH, CO$_2$H, CO$_2$CH$_3$, CH$_2$CO$_2$H, or CH$_2$CO$_2$CH$_3$.

45. The non-peptide protein tyrosine kinase inhibitor according to claim 44, wherein the non-peptide protein tyrosine kinase inhibitor inhibits the activity of pp60$^{c\text{-src}}$ tyrosine kinase.

46. A non-peptide protein tyrosine kinase inhibitor having the formula:

wherein R1 is OH or H, R2 is OH or H, R3 is OH or H, R4 is OH or H, R5 is OH, OMe, or H, R6 is OH, OMe, or H, R7 is OH, OMe, or H, and X is 0 or 1.

47. The non-peptide protein tyrosine kinase inhibitor according to claim 46, wherein R1 is OH, R2 is OH, R3 is H, R4 is H, R5 is OMe, R6 is H, R7 is H, and X is 1.

48. The non-peptide protein tyrosine kinase inhibitor according to claim 46, wherein the non-peptide protein tyrosine kinase inhibitor inhibits the activity of pp60$^{c\text{-src}}$ tyrosine kinase.

49. A non-peptide protein tyrosine kinase inhibitor having the formula:

50. A method of treating a condition, responsive to a protein kinase inhibitor, in a patient comprising:

- 88 -

administering an effective dose of a protein kinase inhibitor to a patient

wherein the protein kinase inhibitor comprises a first module having a functionality

for binding to catalytic residues of the protein kinase and a second module which

provides a non-peptide scaffold, wherein the combination of the first and second

5   modules inhibits protein kinase activity.

51.   The method according to claim 50, wherein the condition is selected

from the group consisting of cancer, psoriasis, arthrosclerosis, or immune system

activity.

10

52.   The method according to claim 50, wherein the first module comprises

a functional group selected from the group consisting of boronic acid, hydroxy,

phosphonic acid, sulfamic acid, a guanidino group, carboxylic acid, an aldehyde, an

amide, and hydroxymethylphosphonic acid.

15

53.   The method according to claim 52, wherein the first module comprises

a boronic acid group.

54.   The method according to claim 52, wherein the first module comprises

20   a hydroxyl group

55.   The method according to claim 50, wherein the second module

comprises a group selected from the group consisting of indole, naphthalene,

biphenyl, isoquinoline, benzofuran, and benzothiophene.

25

56.   The method according to claim 55, wherein the second module

comprises indole.

57.   The method according to claim 55, wherein the second module

30   comprises naphthalene.

58.   The method according to claim 50, wherein more than one first module

is bound to the second module.

59.   The method according to claim 50, wherein a linear chain comprising between one and three carbon atoms links the first module to the second module.

60.   The method according to claim 59, wherein one of the carbon atoms in the linear chain is substituted with a nitrogen, oxygen or sulfur atom.

61.   The method according to claim 50, wherein the protein kinase is a protein tyrosine kinase.

62.   The method according to claim 61, wherein the protein tyrosine kinase is selected from the group consisting of $pp60^{c-src}$, $p56^{lck}$, ZAP kinase, platelet derived growth factor receptor tyrosine kinase, Bcr-Abl, VEGF receptor tyrosine kinase, and epidermal growth factor receptor tyrosine kinase, and epidermal growth factor receptor-like tyrosine kinases.

63.   The method according to claim 62, wherein the protein tyrosine kinase is $pp60^{c-src}$.

64.   The method according to claim 63, wherein the compound has the following formula:

wherein R1 is H or OH, R2 is H or OH, R3 is OH or H, and R4 is CH_3, $CH_2(CH_3)R$, or $CH_2(CH_3)S$, R5 is OCH_3, H, or OH, R6 is OCH_3, F, H, or OH, and R7 is OCH_3, H, OH, CO_2H, CO_2CH_3, CH_2CO_2H, or $CH_2CO_2CH_3$.

65.   The method according to claim 63, wherein the compound has the following formula:

wherein R1 is OH or H, R2 is OH or H, R3 is OH or H, R4 is OH or H, R5 is OH, OMe, or H, R6 is OH, OMe, or H, R7 is OH, OMe, or H, and X is 0 or 1.

66.   The method according to claim 63, wherein the compound has the following formula:

67.   The method according to claim 50, wherein the protein kinase is a protein serine kinase.

68.   The method according to claim 67, wherein the protein serine kinase is selected from the group consisting of MAP kinase, protein kinase C, and CDK kinase.

69.   The method according to claim 50, wherein the compound further comprises one or more specificity side chain elements attached to the combination of the first and second modules.

Figure 1

MODULAR STRATEGY FOR DEVELOPING
NON-PEPTIDE PROTEIN KINASE INHIBITORS

STEP 1

Utilize one or more M_1's to identify promising non-peptide scaffolds.

KEY

M_1 = Module consisting of a selection of validated functionalities for binding to the conserved catalytic residues.

M_2 = Module consisting of a selection of non-peptide scaffolds for PTK's.

S_n = Specificity elements.

STEP 2

Enhance potency with initial specificity elements (S) and validate scaffolds as non-ATP competitive.

STEP 3

Further enhance potency and selectivity via combinatorial libraries optimizing M_1 and specificity elements (S).

$\sim\!\sim\!\sim$ = Optional side chains.

Figure 2
x-ray structure of (PKA):Mg₂ATP:pseudosubstrate inhibitor

In Closed Conformation

Figure 3

**General Module M_1 Design Features For Binding To The Conserved Protein
Kinase Catalytic Region**

Figure 4
SUBSTRATE BEHAVIOR FOR BORONIC ACID PKA INHIBITORS 21 & 22

Figure 5

Binding interactions of src substrate
Ac-Ile-Tyr-Gly-Glu-Phe-NH₂ in model src active site.

Figure 6

Design of naphthalene-based src inhibitor scaffold

src:peptide substrate complex

src:naphthalene-based
non-peptide inhibitor
binding mode

Figure 7

Design of isoquinoline and indole-based src inhibitor scaffolds

src:isoquinoline-based
non-peptide inhibitor
binding mode

src:indole-based
non-peptide inhibitor
binding mode

Figure 8

NMR verification of
triflation regioselectivity

Figure 9

Figure 10

Figure 11

Figure 12

Figure 13
(Residues are from the IRTK ternary structure and dotted bonds are H-bonds)

FIGURE 14

FIGURE 15A   FIGURE 15B

Ovarian Tumor N015 Sensitivity To Drugs: Suspended Cell Culture

Normal Human Fibroblasts Sensitivity To Src Inhibitors: Subconfluent Cell Culture

FIGURE 15C

TOM 2-32   TOM 2-47   KLM 2-31

INTERNATIONAL SEARCH REPORT

International application No.

PCT/US00/00803

A. CLASSIFICATION OF SUBJECT MATTER

IPC(7) :C12Q 1/00, 1/48; G01N 33/543

US CL :435/4, 15; 436/501, 518, 523, 528, 531

According to International Patent Classification (IPC) or to both national classification and IPC

B. FIELDS SEARCHED

Minimum documentation searched (classification system followed by classification symbols)

U.S. : 435/4, 15; 436/501, 518, 523, 528, 531

Documentation searched other than minimum documentation to the extent that such documents are included in the fields searched

Electronic data base consulted during the international search (name of data base and, where practicable, search terms used)

Please See Extra Sheet.

C. DOCUMENTS CONSIDERED TO BE RELEVANT

Category*	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
X --- A	US 5,736,412 A (ZAMBIAS et al.) 07 April 1998, col. 2, lines 37-67.	1 ----- 2-69

☐ Further documents are listed in the continuation of Box C. ☐ See patent family annex.

* Special categories of cited documents:

"A" document defining the general state of the art which is not considered to be of particular relevance

"E" earlier document published on or after the international filing date

"L" document which may throw doubts on priority claim(s) or which is cited to establish the publication date of another citation or other special reason (as specified)

"O" document referring to an oral disclosure, use, exhibition or other means

"P" document published prior to the international filing date but later than the priority date claimed

"T" later document published after the international filing date or priority date and not in conflict with the application but cited to understand the principle or theory underlying the invention

"X" document of particular relevance; the claimed invention cannot be considered novel or cannot be considered to involve an inventive step when the document is taken alone

"Y" document of particular relevance; the claimed invention cannot be considered to involve an inventive step when the document is combined with one or more other such documents, such combination being obvious to a person skilled in the art

"&" document member of the same patent family

Date of the actual completion of the international search	Date of mailing of the international search report
01 MAY 2000	2 4 MAY 2000

Name and mailing address of the ISA/US	Authorized officer
Commissioner of Patents and Trademarks Box PCT Washington, D.C. 20231	MICHAEL PAK
Facsimile No. (703) 305-3230	Telephone No. (703) 308-0196

Form PCT/ISA/210 (second sheet) (July 1998)★

INTERNATIONAL SEARCH REPORT

International application No.
PCT/US00/00803

Box I Observations where certain claims were found unsearchable (Continuation of item 1 of first sheet)

This international report has not been established in respect of certain claims under Article 17(2)(a) for the following reasons:

1. ☐ Claims Nos.:
   because they relate to subject matter not required to be searched by this Authority, namely:

2. ☐ Claims Nos.:
   because they relate to parts of the international application that do not comply with the prescribed requirements to such an extent that no meaningful international search can be carried out, specifically:

3. ☐ Claims Nos.:
   because they are dependent claims and are not drafted in accordance with the second and third sentences of Rule 6.4(a).

Box II Observations where unity of invention is lacking (Continuation of item 2 of first sheet)

This International Searching Authority found multiple inventions in this international application, as follows:

   Please See Extra Sheet.

1. ☒ As all required additional search fees were timely paid by the applicant, this international search report covers all searchable claims.

2. ☐ As all searchable claims could be searched without effort justifying an additional fee, this Authority did not invite payment of any additional fee.

3. ☐ As only some of the required additional search fees were timely paid by the applicant, this international search report covers only those claims for which fees were paid, specifically claims Nos.:

4. ☐ No required additional search fees were timely paid by the applicant. Consequently, this international search report is restricted to the invention first mentioned in the claims; it is covered by claims Nos.:

Remark on Protest ☐ The additional search fees were accompanied by the applicant's protest.

☒ No protest accompanied the payment of additional search fees.

Form PCT/ISA/210 (continuation of first sheet(1)) (July 1998)*

INTERNATIONAL SEARCH REPORT

B. FIELDS SEARCHED

Electronic data bases consulted (Name of data base and where practicable terms used):

BRS, USPT, JPAB, EPAB, DWPI, TDBD, STN, MEDLINE, CAPLUS

search terms: protein kinase inhibitor, tyrosine protein kinase, serine protein kinase, scaffold

BOX II. OBSERVATIONS WHERE UNITY OF INVENTION WAS LACKING

This ISA found multiple inventions as follows:

This application contains the following inventions or groups of inventions which are not so linked as to form a single inventive concept under PCT Rule 13.1. In order for all inventions to be searched, the appropriate additional search fees must be paid.

Group I, claim(s) 1-20, drawn to a method for identifying inhibitors of protein kinase.
Group II, claim(s) 21-22, drawn to a method for identifying improved protein kinase inhibitors.
Group III, claim(s) 23, drawn to a method for testing compounds for an ability to inhibit protein kinase.
Group IV, claim(s) 24-43, drawn to a method of inhibiting of protein kinase.
Group V, claim(s) 44-49, drawn to a non-peptide protein tyrosine kinase inhibitor.
Group IV, claim(s) 50-69, drawn to a method of treating a condition, responsive to a protein kinase inhibitor.

The inventions listed as Groups I-VI do not relate to a single inventive concept under PCT Rule 13.1 because, under PCT Rule 13.2, they lack the same or corresponding special technical features because the method of claim 1 is anticipated by ZAMBIAS et al. (US 5,736,412) and thus, does not share a special technical feature with any other group.

The methods of Groups II-V and VI, do not share the same or corresponding special technical feature with Group I, because the methods have materially different process steps and are practiced for materially different purposes, and each defines a separate invention over the art.

The product of Group V do not share the same or corresponding special technical feature with Group I, because the product of Group V can be used in a materially different process in the alternative of any one of groups II-V or VI.

Since Groups I-VI do not share a special technical feature, unity of invention is lacking.